


NEW 3 5/8" MTL  
STUDS; SIZE  
GAUGE PER  
MANUF.  
RECOMM. AND  
SPACE 16" O.C.;  
1/2" TK GPDW  
BOTH SIDES;  
FILL W/ FULL  
SOUND BATT  
INSUL.



NEW 3 5/8" MTL  
STUDS; SIZE  
GAUGE PER  
MANUF.  
RECOMM. AND  
SPACE 16" O.C.;  
5/8" TK TYPE 'X'  
F.R. GPDW BOTH  
SIDES; FILL W/  
FULL SOUND  
BATT INSUL.



ALL PARTITIONS  
U.O.N.



1 HOUR FIRE RATED  
PARTITION



SIM. BUT USE 6" MTL  
STUDS.



1 HOUR FIRE RATED  
PARTITION W/ 6" MTL STUDS

PARTITION TYPES

NOTES:

1. SOUND PROOF- STAGGER OUTLETS ON OPP. SIDES, ETC. AND TEST AFTER INSTALLATION FOR SOUND PROOF.
2. SEAL ALL WALLS AT COLUMNS, BEAMS & DECK TIGHT TO MAKE SMOKE PROOF. ALL WALLS TO GO UP TO DECK; THEREFORE, INFILL BETWEEN JOISTS IF NECESSARY. USE ACOUSTICAL SEALANT IF NO FIRE RATING, USE FIRE RETARDENT SEALANT AT HALLS AND ANY RATED WALL.

Project Title BLAZE LLC TENANT SPACE		J.B. Brown & Sons, Inc. 36 Danforth Street Portland ME 04101		Drawing Title DOORS, WINDOWS, ETC.		Drawing Number A5.1d	
bell edu	Copyright 2012 Michael Belleau Architect 61 Pleasant Street Portland ME 04101 (207)874-7668 www.michaelbelleau.com			Date:	6/20/12	Scale:	AS SHOWN
				Project Number:	12.05	Reference:	NONE