Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 07/12/13

LOCATE DOORBELL DISABLE SWITCH NEXT TO WELCOME LIGHT SWITCH - DO NOT GANG BOX. PROVIDE SEPARATE LABELED COVERPLATE (TYPICAL)

7 / E13 HEARING DEVICE TYPICAL LAYOUT
1/4" = 1'-0"

DEVICES FOR THE HEARING IMPAIRED

SYMBOL	DEVICE	NOTES
J PB	BUTTON FOR DOOR SIGNAL	OUTSIDE DOOR ON STRIKE SIDE, +48" AFF FACTORY LABEL ON COVER PLATE
J T	2-GANG BOX WITH TRANSFORMER FOR DOOR BELL	MOUNT IN SOFFIT OR CABINET – PROVIDE ACCESS
DDS	DOORBELL DISABLE SWITCH	WALL BEHIND ENTRY DOOR, GANG W/ LIGHT SWITCH "DOORBELL DISABLE SWITCH" PLAQUE
H G	POINT ADDRESSIBLE SMOKE DETECTOR W/ SOUNDER BASE	MOUNT 4" – 12" BELOW CEILING "FIRE" LABEL INTEGRAL TO DEVICE.
A A H	HORN STROBE FOR DOOR SIGNAL	MOUNT 80" AFF
▽	REMOTE STROBE FIRE/DOOR SIG	MOUNT 80" AFF

NOTES:

PROVIDE ASSISTIVE LISTENING DEVICES IN THE REQUIRED NUMBER OF ROOMS PER BUILDING CODES AND ADAAG 2004.

1. DISTRIBUTE HEARING IMPAIRED ROOMS AMONGST ALL CLASSES OF ROOMS INCLUDING SUITES.
2. PLAQUES (EXCEPT AS NOTED): PROVIDE AS INDICATED. PLAQUES SHALL BE BLACK PHENOLIC WITH 1/4" WHITE ENGRAVED LETTERS.

REFERENCE NOTES

1. REFER TO SPECIFICATIONS FOR FINISH INDEX
2. REFER TO ENLARGED PLANS FOR PARTITION TYPES AT PUBLIC SPACE ADJACENCIES
3. REFER TO SHEET A0.4 FOR PARTITION ASSEMBLY TYPES
4. REFER TO SHEET E0 FOR ELECTRICAL SYMBOLS LEGEND
5. ELECTRICAL OUTLETS SHOWN ON ELEC/PLUMBING/MECH PLAN AND ON ELEVATIONS ARE FOR DEVICES AND FIXTURES SPECIFIED. ADDITIONAL OUTLETS MAY BE REQUIRED BY LOCAL BUILDING CODES.
6. ELECTRICAL OUTLETS ARE MOUNTED AT STANDARD HEIGHT OF 18" UNLESS NOTED OTHERWISE.
7. SWITCHES AND THERMOSTATS TO BE LOCATED AT 46" AFF UNLESS NOTED OTHERWISE.
8. REFER TO GUESTROOM ELEVATIONS FOR MOUNTING CONFIGURATIONS OF OUTLETS. COORDINATE FINAL LOCATIONS WITH CASEGOODS.
9. DIMENSIONING IS BASED ON WALL ASSEMBLIES SHOWN ON SHEET A0.4 AND ON ENLARGED PLANS. ALL DIMENSIONS ARE FROM FACE OF FINISH TO FACE OF FINISH, U.N.O. HOLD ALL CLEAR INTERIOR ROOM DIMENSIONS.
10. WATER CLOSET WASTE LINES ARE TO BE LOCATED IN WALL CHASE, NOT IN EXTERIOR WALLS
11. REFER TO SHEET A7.1 FOR ACCESSIBLE GUESTROOM PLUMBING FIXTURE & MOUNTING HEIGHT REQUIREMENTS NOT SHOWN ON ELEVATIONS

CRITERIA NOTES

1. NOT USED.
2. WHERE DRAPERY RODS ARE USED AT WINDOWS OR SLIDING DOORS, PROVIDE CONTINUOUS SOLID WOOD BLOCKING IN CEILING FOR ATTACHMENT.
3. ALL EXTERIOR CORNERS SHALL HAVE FULL HEIGHT CORNER GUARDS (382) PER FINISH INDEX. SEE ELEVATIONS.
4. IRONING BOARD AND IRON RACK MOUNTED INSIDE OF CLOSET.
5. PLUG TABLE LAMP INTO THIS OUTLET, OPTIONAL.
6. SHELF AND CLOSET ROD
7. GANG OUTLETS AND SWITCHES AT THIS LOCATION @ HEIGHT SHOWN.
8. WALL OUTLETS SHALL NOT OCCUR IN SAME WALL CAVITY OF ADJACENT GUESTROOMS, TYPICAL.
9. PROVIDE BLOCKING FOR ACCESSORIES.
10. START WITH FULL TILE WHERE SHOWN.
11. NOT USED.
12. TUB/SHOWER LIGHT LOCATION (SWITCH WITH MAIN ROOM LIGHT). WHEN CONTINUOUS VENTING IS USED, INSTALL LIGHT ONLY, R47.
13. OPTIONAL PHONE OUTLET FOR DESK.
14. OPTIONAL DEDICATED OUTLET FOR OPTIONAL MICROWAVE.
15. GRAPHIC WALL MURAL. REFERENCE IF1 FOR OPTIONS.
16. MASTER LIGHT SWITCH WITH SIGNAGE TO CONTROL ALL HARDWIRED LIGHTS IN GUESTROOM, WITH EXCEPTION OF BATHROOM.
17. INSTALL STRAIGHT CURTAIN ROD AT THIS OPTION.
18. AT HEARING IMPAIRED ROOM ONLY.
19. NOT USED.
20. NOT USED.
21. TEXTURED FINISH. AT EXTERIOR WALL, USE (379)
22. RUN TILES TO CEILING & SCRIBE.
23. PROVIDE CAT 5E CABLE TO JUNCTION BOX – NO CONNECTED DEVICE – WITH BLANK FACEPLATE FOR FUTURE USE.
24. ATTACH ROBE HOOK TO GLASS PANEL.
25. DRAPERY PULL WANDS ARE LOOP TYPE HANDLES AND 48" MAX AFF
26. COORDINATE LOCATION OF GRAPHIC WALL MURAL WITH ROBE HOOK LOCATION.
27. INSTALL STRAIGHT CURTAIN ROD AT THIS OPTION.
28. PROVIDE MILLWORK BASE FOR REFRIGERATOR TO SIT ON.
29. WRAP DRAINAGE AND SUPPLY PIPES WITH INSULATING MATERIAL
30. REFER TO SHEET 500 SERIES SHEETS FOR MILLWORK DETAILS
31. DESIGNER TO COORDINATE WINDOW LOCATION AND PTAC LOCATION WITH DIMENSIONS AND LOCATION OF HOSPITALITY CABINET
32. PROVIDE CORNER GUARDS ON ALL OUTSIDE CORNER, (380) TYP WHERE VWC (305) IS USED
33. PAINT GUESTROOM CEILINGS (401), PORTAL CEILINGS (350), & BATHROOM CEILINGS (400)

6 / A8 KING SUITE-CORNER
1/4" = 1'-0"

8 / A8 TYPICAL ACCESSIBLE KING
1/4" = 1'-0"

4 / E13 KING-CORNER
1/4" = 1'-0"

3 / E13 TYPICAL Q/Q W/SHOWER
1/4" = 1'-0"

2 / E13 TYPICAL Q/Q W/TUB
1/4" = 1'-0"

1 / E13 TYPICAL KING
1/4" = 1'-0"

REVISION SCHEDULE		
DATE	REVISION DESCRIPTION	BY

© COPYRIGHT 2012 BY O.C.C.

CONSTRUCTION CORPORATION
11 CORPORATE DRIVE, BELMONT NH 03220
PHONE (603) 527-9090 FAX (603) 527-9191

GUESTROOM POWER PLANS

PROJECT:
COMMERCIAL & MAPLE STREET
MIXED USE DEVELOPMENT
PORTLAND, ME

DATE: 06-26-13
SCALE: SEE PLAN
DRAWN BY: KPH

SHEET: E13