



PROVIDE 10 MIL POLY VAPOR BARRIER ON POOL SIDE OF WALLS AND CEILING. SEAL ALL JOINTS, PENETRATIONS AND SEAMS. SEE ADDITIONAL NOTES ON DWS. A22.

PROVIDE WATERPROOFING MEMBRANE AT THE BASE OF ALL POOL ROOM WALLS-SEE DETAIL 2/A11.

ALL COLUMNS AT FIRST FLOOR LEVEL TO BE PROTECTED FOR THEIR FULL LENGTH AS DETAILED ON DWS. A01 FOR 3 HR. FIRE RESISTANCE RATING.

INTERIOR HALLS TO BE HALL TYPE 2 UNLESS NOTED OTHERWISE.

* AT WALLS NOTED WITH THIS SYMBOL, PROVIDE 5/8" TILE BACKER BOARD FOR THIN BRICK VENEER FINISH AT WINDOW OPENINGS-HRAP TO MEET WINDOW FRAMES.

| DATE | REVISION DESCRIPTION |
|----------|---|
| 04-27-13 | REVISED WALK WALLS, FIRE-RATED WALL AT ELEVATORS, LOBBY, DELETED DOOR W/KA @ OFFICE AREA, ADDED SHELF AT LUGGAGE STORAGE. |
| 10-17-13 | DELETED POOL PATIO ENCLOSURE. |
| 01-30-14 | ADDED BIKE STORAGE ROOM AT RESIDENCE ELEVATOR LOBBY. IELB2 |

LOPECHEE
 CONSTRUCTION CORPORATION
 11 CORPORATE DRIVE, BELMONT NH 03220
 PHONE (603) 527-9090 FAX (603) 527-9191

FIRST FLOOR PLAN

PROJECT: **COMMERCIAL & MAPLE STREET MIXED USE DEVELOPMENT**
 PORTLAND, ME

| |
|-----------------|
| DATE: 05-09-13 |
| SCALE: SEE PLAN |
| DRAWN BY: KPH |
| A1 |
| SHEET: |

FIRST FLOOR PLAN
 1/8" = 1'-0"
 PLAN