



CTT 0600L44 DEFROST UNIT,  
 FINAL LOCATION BY OTHERS.  
 BLOCK UNIT ON FLAT OF ROOF  
 PANELS WITH 4x4x5' MEMBERS  
 SPANNING THREE JOIST AS  
 INDICATED. SHIM UNIT TO LEVEL  
 AND FASTEN TO BLOCKING WITH  
 LAG SCREWS. IF DESIRED,  
 THROUGH BOLT BLOCKING TO TOP  
 CHORD OF JOISTS AT FOUR POINTS.

TWO CTT 2200L44 UNITS,  
 FINAL LOCATION BY OTHERS.  
 BLOCK UNIT ON FLAT OF ROOF  
 PANELS WITH 4x4x5' MEMBERS  
 SPANNING THREE JOIST AS  
 INDICATED. SHIM UNIT TO LEVEL  
 AND FASTEN TO BLOCKING WITH  
 LAG SCREWS. IF DESIRED,  
 THROUGH BOLT BLOCKING TO TOP  
 CHORD OF JOISTS AT FOUR POINTS.

VESSEL SERVICES ROOFTOP NEW UNIT LOCATION PLAN  
 RAJP, 25 JANUARY 2012