C1
3"Ø SCH 40 PIPE COLUMN
1"= 1'-0"

C2
3"Ø SCH 40 PIPE COLUMN
1"= 1'-0"

C3
HSS 6x6x1/4 COLUMN
1"= 1'-0"

C4
HSS 6x6x1/4 COLUMN
1"= 1'-0"

C4
HSS 6x6x1/4 COLUMN
1"= 1'-0"

VIEW D-D
3"= 1'-0"

VIEW E-E
3"= 1'-0"

bp-2
5/8" PLATE
3"= 1'-0"

cc-1
3"= 1'-0"
⅜" PLATE
3"ø COLUMN CLIP
(4) FOUR REQ'D.

cc-2
3"= 1'-0"
⅜" PLATE
3"ø COLUMN CLIP
(2) TWO REQ'D.

cc-3
3"= 1'-0"
L3x3x¼
JAMB CLIP
(8) EIGHT REQ'D.

bp-3
3"= 1'-0"
⅜" PLATE
ANGLE BRACE BASE PLATE
(1) ONE REQ'D.

bp-1
3"= 1'-0"
½" PLATE
3"ø COLUMN BASE PLATE
(4) FOUR REQ'D.

MATERIAL SCHEDULE

SHIPPING MARK	NO. PCS.	SUB-ASSEM.	SHAPE	LENGTH FT.	LENGTH IN.	D OR S	CUT FROM NO.	CUT FROM FT.	CUT FROM IN.	REMARKS	WT.
C1	2		3"ø SCH 40	10	8¼					COLUMN 1	
	2	cc-1	⅜" PLATE		6⅞					COLUMN CLIP	
	1	bp-1	½" PLATE		9½					BASE PLATE	
C2	2		3"ø SCH 40	10	8¼					COLUMN 1	
	1	cc-2	⅜" PLATE		9½					COLUMN CLIP	
	1	bp-1	½" PLATE		9½					BASE PLATE	
C3	1		HSS 6x6x¼	9	11⅜					DEMISING WALL COLUMN	
	2	cc-3	L3x3x¼		4					COLUMN CLIP	
	1	bp-2	5/8" PLATE	1						BASE PLATE	
C4	1		HSS 6x6x¼	9	11⅜					DEMISING WALL COLUMN	
	1	cc-3	L3x3x¼		4					COLUMN CLIP	
	1	bp-2	5/8" PLATE	1						BASE PLATE	
	1	ab-1	L3x3x¼	3	7⅜					ANGLE BRACE	
	28		½"ø		1½					ASTM A325 BOLT	
										TOTAL WEIGHT	

PRINT DISTRIBUTION

MATERIAL	STEEL FABRICATION	HOLES	AS NOTED
BOLTS	ASTM A325	ELECTRODE	E70X
SURFACE PREP		REF. DWG.	S-101, S-103, S-103
PRIMER			
FINISH			

THE SHERIDAN CORPS.
FAIRFIELD - PORTLAND
MAINE

DESCRIPTION	STEEL FABRICATION
PROJECT	STAIR RELOCATION AND DEMISING WALL CONSTRUCTION
LOCATION	PORTLAND, MAINE
DESIGNER	RDL
CUSTOMER	BRISTOL SEAFOOD

REV.			
CHK'D			
DRWN	05-10-13	JOB NO. M-131003	DWG. NO. F-102	REV.

AUTOCAD® FILE NAME:

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 05/30/13