R4
1 1/4"Ø SCH 40 PIPE RAIL
1"= 1'-0"

R5
1 1/4"Ø SCH 40 PIPE RAIL
1"= 1'-0"

# MATERIAL SCHEDULE

| SHIPPING MARK | NO. PCS. | SUB-ASSEM. | SHAPE | LENGTH FT. | LENGTH IN. | O OR S | CUT FROM NO. | CUT FROM FT. | CUT FROM IN. | REMARKS | WT. |
|---|---|---|---|---|---|---|---|---|---|---|---|
| R4 | 1 | | 1¼"ø SCH 40 | 39 | | | | | | BEAM 4 – RAILING | |
| R5 | 1 | | 1¼"ø SCH 40 | 56 | | | | | | BEAM 5 – RAILING | |
| | | | | | | | | | | TOTAL WEIGHT | |

PRINT DISTRIBUTION

| | |
|---|---|
| MATERIAL | STEEL FABRICATION |
| HOLES | AS NOTED |
| BOLTS | ASTM A325 |
| ELECTRODE | E70X |
| SURFACE PREP | |
| REF. DWG. | S–101, S–103, S–103 |
| PRIMER | |
| FINISH | |

THE SHERIDAN CORPS.
FAIRFIELD – PORTLAND
MAINE

| | |
|---|---|
| DESCRIPTION | RAILING FABRICATION |
| PROJECT | STAIR RELOCATION AND DEMISING WALL CONSTRUCTION |
| LOCATION | PORTLAND, MAINE |
| DESIGNER | RDL |
| CUSTOMER | BRISTOL SEAFOOD |

| | |
|---|---|
| REV. | |
| CHK'D | |
| DRWN | 05–10–13 |

JOB NO. M–131003 | DWG. NO. F–105 | REV.

AUTOCAD® FILE NAME:

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 05/30/13