B1

C15x33.9 CATWALK BEAM
1"= 1'-0"

B2

C15x33.9 CATWALK BEAM
1"= 1'-0"

B3

C15x33.9 CATWALK BEAM
1"= 1'-0"

B6

C15x33.9 CATWALK BEAM
1"= 1'-0"

B4

C15x33.9 CATWALK BEAM
1"= 1'-0"

B5

C15x33.9 CATWALK BEAM
1"= 1'-0"

bc-1

3"= 1'-0"

L3x3x5/16
CHANNEL CLIP
(8) EIGHT REQ'D.

MATERIAL SCHEDULE

SHIPPING MARK	NO. PCS.	SUB-ASSEM.	SHAPE	LENGTH FT.	LENGTH IN.	D OR S	CUT FROM NO.	CUT FROM FT.	CUT FROM IN.	REMARKS	WT.
B1	1		C 15x33.9	22	11 3/8					BEAM 1 – CATWALK BEAM	
	4	bc-1	L3x3x5/16		3 1/2					BEAM CLIP	
	1	bc-2	L3x3x5/16		8 1/2					BEAM CLIP	
	1	jc-1	L2x2x1/4	21	1 1/8					JOIST CLIP	
B2	1		C 15x33.9	19	11 1/2					BEAM 2 – CATWALK BEAM	
	4	bc-1	L3x3x5/16		3 1/2					BEAM CLIP	
	1	bc-2	L3x3x5/16		8 1/2					BEAM CLIP	
	1	jc-2	L2x2x1/4	19	4 1/8					JOIST CLIP	
B3	1		C 15x33.9	3	4 3/4					BEAM 3 – CATWALK BEAM	
	1	jc-3	L2x2x1/4	2	5 1/8					JOIST CLIP	
B4	1		C 15x33.9	19	11 1/2					BEAM 4 – CATWALK BEAM	
	1	jc-4	L2x2x1/4	14	7					JOIST CLIP	
	1	jc-5	L2x2x1/4	3	0 3/4					JOIST CLIP	
B5	1		C 15x33.9	21	8 1/2					BEAM 5 – CATWALK BEAM	
	1	jc-6	L2x2x1/4	20	3 3/4					JOIST CLIP	
B6	1		C 15x33.9	3	4 3/4					BEAM 6 – CATWALK BEAM	
	1	jc-6	L2x2x1/4	2	5 1/8					JOIST CLIP	
	28		5/8"ø		2					ASTM A325 BOLT	
	28		1/2"ø		1 1/2					ASTM A325 BOLT	
	24		5/8"ø		10 1/2					ANCHOR BOLT	
	10		1/2"ø		6 1/2					ANCHOR BOLT	
	18		#4		14					DOWEL	
	??		12-24		1 5/8					PLYWOOD TO STEEL JOIST	
	??		12-24		2 3/4					WOOD NAILER TO C15x33.9	
	??		12-14		3/4					METAL JOIST TO L2x2x1/4	
	??		PANEL RIVET		3/4					KEMPLY PANEL FASTENER	
										TOTAL WEIGHT	

PRINT DISTRIBUTION

MATERIAL	STEEL FABRICATION
BOLTS	ASTM A325
SURFACE PREP	
PRIMER	
FINISH	
HOLES	AS NOTED
ELECTRODE	E70X
REF. DWG.	S-101, S-103, S-103

THE SHERIDAN CORPS.
FAIRFIELD – PORTLAND
MAINE

DESCRIPTION	STEEL FABRICATION
PROJECT	STAIR RELOCATION AND DEMISING WALL CONSTRUCTION
LOCATION	PORTLAND, MAINE
DESIGNER	RDL
CUSTOMER	BRISTOL SEAFOOD
REV.	
CHK'D	
DRWN	05-10-13
JOB NO.	M-131003
DWG. NO.	F-101
REV.	

AUTOCAD® FILE NAME:

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 05/30/13