CH1 - DEMISING WALL JAMB

C6x8.2
1 1/2"= 1'-0"
(3) THREE REQ'D.

CH2 - DEMISING WALL HEADER

C6x8.2
1"= 1'-0"
(1) ONE REQUIRED
CHANNEL MAY REQUIRE FIELD CUTTING AND DRILLING

CH3 - DEMISING WALL HEADER

C6x8.2
1"= 1'-0"
(1) ONE REQUIRED
CHANNEL MAY REQUIRE FIELD CUTTING AND DRILLING

CH4 - DEMISING WALL JAMB

C6x8.2
1"= 1'-0"
(1) ONE REQUIRED
CHANNEL MAY REQUIRE FIELD CUTTING AND DRILLING

cc-3

3"= 1'-0"
L3x3x¼
JAMB CLIP
(8) EIGHT REQ'D.

cc-4

3"= 1'-0"
L6x3½x5/16
JAMB CLIP
(3) THREE REQ'D.

cc-5

3"= 1'-0"
L5x3x¼
JAMB CLIP
(?) ??? REQ'D.

MATERIAL SCHEDULE

SHIPPING MARK	NO. PCS.	SUB-ASSEM.	SHAPE	LENGTH FT.	LENGTH IN.	D OR S	CUT FROM NO.	CUT FROM FT.	CUT FROM IN.	REMARKS	WT.
CH1	3		C6x8.2	9	9 13/16					DEMISING WALL JAMB	
	1	cc-3	L3x3x¼		4					JAMB CLIP	
	1	cc-4	L6x3½x5/16		4					JAMB CLIP	
CH2	1		C6x8.2	17	9					DEMISING WALL HEADER	
CH3	1		C6x8.2	16	3⅞					DEMISING WALL HEADER	
CH4	1		C6x8.2	9	9 13/16					DEMISING WALL JAMB	
	1	cc-3	L3x3x¼		4					JAMB CLIP	
	2	cc-5	L5x3x¼		4					JAMB CLIP	
										TOTAL WEIGHT	

PRINT DISTRIBUTION

MATERIAL	STEEL FABRICATION
HOLES	AS NOTED
BOLTS	ASTM A325
ELECTRODE	E70X
SURFACE PREP	
REF. DWG.	S-101, S-103, S-103
PRIMER	
FINISH	

THE SHERIDAN CORPS.
FAIRFIELD - PORTLAND
MAINE

DESCRIPTION	STEEL FABRICATION
PROJECT	STAIR RELOCATION AND DEMISING WALL CONSTRUCTION
LOCATION	PORTLAND, MAINE
DESIGNER	RDL
CUSTOMER	BRISTOL SEAFOOD

REV.
CHK'D
DRWN 05-10-13

JOB NO. M-131003 | DWG. NO. F-103 | REV.

AUTOCAD® FILE NAME:

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 05/30/13