DOOR & FRAME SCHEDULE

General			Door			Frame			Details					
Door No.	Size (W x H)	Thickness	Material	Finish	Type	Material	Finish	Type	Head	Jamb	Threshold	Hardware	Label	Remarks
SECOND FLOOR														
101	3'-0" X 7'-0"	1 3/4"	ALUM	Exist'g	Exist'g	ALUM	Exist'g	Exist'g	Exist'g	Exist'g	ALUM THRSH	HDWR 3	--	
102	3'-0" X 7'-0"	1 3/4"	ALUM	F.F.	B	ALUM	F.F.	F3	H3	J3	ALUM THRSH	HDWR 3	--	
103	3'-0" X 7'-0"	1 3/4"	SCWD	CLR. F.	A	HM	PNTD.	F1	H2	J2	--	HDWR 4	--	
104	3'-0" X 7'-0"	1 3/4"	SCWD	PNTD.	A	HM	PNTD.	F1	H1	J1	T1	HDWR 1	--	1" Undercut
105	3'-0" X 7'-0"	1 3/4"	SCWD	PNTD.	A	HM	PNTD.	F1	H1	J1	T1	HDWR 1	--	1" Undercut
106	3'-0" X 7'-0"	1 3/4"	SCWD	PNTD.	C	HM	PNTD.	F1	H4	J4	T2	HDWR 2	--	2 way swing door
107	2'-10" X 7'-0"	1 3/4"	GHM	PNTD.	A	GHM	PNTD.	F2	H4	J4	ALUM THRSH	HDWR 3	--	Verify exist'g. M.O. dims

Hardware Sets:

HDWR 1: Hinges, Silencers, Stop, Commercial Duty Lever Lockset - Passage Function.
HDWR 2: 2 way swinging, self closing hinges, push plates and kick plate each side.
HDWR 3: Hinges, Closer, Stop, Exit Device, Entrance Function Lockset, Kick Plate, Weatherstripping
HDWR 4: Hinges, Closer, Silencers, Stop, Commercial Duty Lever Lockset - Office Function.

ABBREVIATIONS

ALUM	Aluminum
SCWD	Solid Core wood door
CLR. F.	Clear Finish
HM	Hollow Metal
GHM	Galvanized Hollow Mtl.
PNTD.	Painted
F.F.	Factory Finish
HW	Hardware Set
TG	Tempered Glass

DOOR TYPES
1/4" = 1'-0"

F3 Elevation View from Exterior

FRAME TYPES
1/4" = 1'-0"

TRANSITION DETAILS
3"= 1'-0"

H4 J4 JAMB DETAIL (Head Similar)

H3 J3 JAMB DETAIL AT ALUMINUM STOREFRONT (Head Similar)
SCALE: 3" = 1'-0"

H1 J1 Note: At Door 106 Provide frame w/ no stops (2 way swing door)

H2 J2 FIELD VERIFY FRAME DEPTH

FRAME DETAILS
3"= 1'-0"

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 08/20/13

WSA
WINTON SCOTT ARCHITECTS
5 Milk Street
Portland, Maine 04101
207 774 4811
www.wintonscott.com

REGISTERED ARCHITECT WINTON F. SCOTT, JR. No. 793 STATE OF MAINE

KING'S HEAD
Tenant Fit Up

Merrill's Wharf
Portland, Maine

REVISIONS
5/9/13
6/8/13

PERMIT DOCUMENTS
JUNE 8, 2013

Door Schedule / Details
Scale: As Noted

A 601