

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

WATERFRONT MAINE /RB Allen

Located at

252 COMMERCIAL ST

PERMIT ID: 2014-00999

ISSUE DATE: 05/27/2014

CBL: 041 A016001

has permission to **Install Fire Alarm system for the Kings Head Pub.**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise cloed-in. 48 HOUR NOTICE IS REQUIRED.	A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.
--	--

/s/ Chris Pirone

/s/ Tammy Munson

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Building Inspections

Fire Department

Suite 100; Unit L - restaurant use

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

**Check the Status or Schedule an Inspection On-Line at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2014-00999	Date Applied For: 05/12/2014	CBL: 041 A016001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Same: Suite 100 - uit "L" is restaurant use		Proposed Project Description: Install Fire Alarm system for the Kings Head Pub.		
Dept: Zoning Status: Approved Reviewer: Marge Schmuckal Approval Date: 05/13/2014		Ok to Issue: <input checked="" type="checkbox"/>		
Note:				
Conditions:				
Dept: Fire Status: Approved w/Conditions Reviewer: Chris Pirone Approval Date: 05/23/2014		Ok to Issue: <input checked="" type="checkbox"/>		
Note:				
Conditions:				
<p>1) The approved plans with the Building Department Approved stamp shall be maintained on site for inspection.</p> <p>2) Notice: The first scheduled final inspection fee is at no charge. Additional inspections shall be billed at \$75 for each inspector.</p> <p>3) Supervising Station monitoring for addressable fire alarm systems shall be by point.</p> <p>4) FACP, annunciator(s), and pull stations shall be keyed alike.</p> <p>5) All fire alarm records required by NFPA 72 should be stored in an approved cabinet located at the FACP labeled "FIRE ALARM RECORDS".</p> <p>6) Visible signals are required per NFPA 101:9.6.3.5 in accordance with NFPA 72:18.5.4.4. Audible and visible notification signals are not required in exit stair enclosures by NFPA 101:9.6.3.5.5 and NFPA 101:9.6.3.6.4.</p> <p>7) In field installation shall be installed per code as conditions dictate.</p> <p>8) The fire alarm system shall have a new fire alarm inspection sticker.</p> <p>9) The installation shall comply with the following: City of Portland Chapter 10, Fire Prevention and Protection; NFPA 1, Fire Code (2009 edition), as amended by City Code; NFPA 101, Life Safety Code (2009 edition), as amended by City Code; City of Portland Fire Department Rules and Regulations; NFPA 72, National Fire Alarm and Signaling Code (2010 edition), as amended by Fire Department Rules and Regulations; and NFPA 70, National Electrical Code (2011 edition) as amended by the State of Maine</p> <p>10 All smoke detectors shall be photoelectric.</p> <p>11 Through-penetrations and membrane penetrations in fire walls, fire barrier walls, and fire resistance rated horizontal assemblies shall be protected by firestop systems or devices in conformance with NFPA 101:8.3.5 (ASTM E 814 or ANSI/UL 1479). Providing firestop labels at each firestop system or device and an onsite manual containing the detail for each firestop system or device used for the project will streamline final inspection approvals.</p> <p>12 The fire alarm technician shall be present for the fire inspection. System acceptance and commissioning must be coordinated with alarm and suppression system contractors and the Fire Department. Call 874-8400 to schedule.</p> <p>13 Fire protection systems shall be maintained. If system is to be off line over 4 hours a fire watch shall be in place. Dispatch notification required 874-8576.</p>				