

SECTION 09 65 00
RESILIENT FLOORING

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes the following:
 - 1. Rubber treads, risers and landing tile.
 - 2. Vinyl composition floor tile.
 - 3. Rubber wall base and accessories.

1.2 PERFORMANCE REQUIREMENTS

- A. Static Coefficient of Friction: For flooring installed on walkway surfaces, provide products with the values indicated as determined by testing identical products per ASTM C 1028.

1.3 SUBMITTALS

- A. Product Data: For each type of product specified.
- B. Samples for Selection: Manufacturer's color charts consisting of units or sections of units showing the full range of colors and patterns available for each type of product indicated.
 - 1. For resilient accessories, manufacturer's standard-size samples, but not less than 12 inches long, of each resilient accessory color and pattern specified.
 - 2. For heat-welding bead, manufacturer's standard-size Samples, but not less than 9 inches long, of each color required.
- C. Seam Samples: For seamless-installation technique indicated and for each floor covering product, color, and pattern required; with seam running lengthwise and in center of 6-by-9-inch Sample applied to a rigid backing and prepared by Installer for this Project.
- D. Product Certificates: Signed by manufacturers of resilient products certifying that each product furnished complies with requirements.
- E. Maintenance Data: For resilient flooring to include in the maintenance manuals specified in Division 1.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified installer who employs workers for this Project who are competent in techniques required by manufacturer for floor covering installation and seaming method indicated.
 - 1. Engage an installer who employs workers for this Project who are trained or certified by floor covering manufacturer for installation techniques required.

- B. Source Limitations: Obtain each type, color, and pattern of product specified from one source with resources to provide products of consistent quality in appearance and physical properties without delaying the Work.
- C. Fire-Test-Response Characteristics: Provide products with the following fire-test-response characteristics as determined by testing identical products per test method indicated below by a testing and inspecting agency acceptable to authorities having jurisdiction.
 - 1. Critical Radiant Flux: 0.45 W/sq. cm or greater when tested per ASTM E 648.
 - 2. Smoke Density: Maximum specific optical density of 450 or less when tested per ASTM E 662.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Deliver products to Project site in manufacturer's original, unopened cartons and containers, each bearing names of product and manufacturer, Project identification, and shipping and handling instructions.
- B. Store products in dry spaces protected from the weather, with ambient temperatures maintained between 50 and 90 deg F.
- C. Store tiles on flat surfaces. Do not stake boxes of tiles over 5 high.
- D. Store rolls upright.
- E. Move products into spaces where they will be installed at least 48 hours before installation, unless longer conditioning period is recommended in writing by manufacturer.

1.6 PROJECT CONDITIONS

- A. Maintain a temperature of not less than 70 deg F or more than 95 deg F in spaces to receive products for at least 48 hours before installation, during installation, and for at least 48 hours after installation, unless manufacturer's written recommendations specify longer time periods. After postinstallation period, maintain a temperature of not less than 55 deg F or more than 95 deg F.
- B. Do not install products until they are at the same temperature as the space where they are to be installed.
- C. Close spaces to traffic during flooring installation and for time period after installation recommended in writing by manufacturer.
- D. Install products and accessories after other finishing operations, including painting, have been completed.
- E. Where demountable partitions and other items are indicated for installation on top of resilient tile flooring, install tile before these items are installed.
- F. Do not install flooring over concrete slabs until slabs have cured and are sufficiently dry to bond with adhesive, as determined by flooring manufacturer's recommended bond and moisture test as well as acceptable pH range.

1.7 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed, are packaged with protective covering for storage, and are identified with labels describing contents.
 - 1. Furnish not less than one box of each type, color, pattern, class, wearing surface, and size of resilient tile flooring installed.
 - 2. Furnish not less than 10 linear feet in roll form of each different composition, wearing surface, color, and pattern of sheet floor covering installed.
 - 3. Furnish not less than 10 linear feet for each type, color, pattern, and size of resilient accessory installed.
 - 4. Deliver extra materials to Owner.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, those indicated in the following paragraphs of Part 2.

2.2 RUBBER FLOOR TILE

- A. Rubber Floor Tile: Where this designation is indicated, provide molded-rubber floor tile complying with ASTM F 1344 and the following:
 - 1. Available Products: As follows:
 - a. Johnsonite; Roundel Solid Color Rubber Flooring.
 - 2. Color and Pattern: As selected by Architect from manufacturer's full range of colors and patterns produced for tile complying with requirements indicated.
 - 3. Class: Class I-A (homogenous rubber tile, solid color).
 - 4. Hardness: Durometer hardness not less than 85 Shore, Type A per ASTM D 2240 as required according to ASTM F 1344.
 - 5. Static Coefficient of Friction: Ramp Surfaces: Minimum 0.8.
 - 6. Thickness: 1/8 inch.
 - 7. Size: 24 by 24 inches.
 - 8. Molded-Pattern Figure: Low profile raised discs.

2.3 RESILIENT TILE

- A. Vinyl Composition Tile: Where this designation is indicated, provide vinyl composition floor tile complying with ASTM F 1066 and the following:
 - 1. Products: As follows:
 - a. Armstrong World Industries: Excelon Stonetex.
 - 2. Color and Pattern: As selected by Architect from manufacturer's full range of colors and as indicated on the drawings.
 - 3. Class: Class 2 (through-pattern tile).
 - 4. Static Coefficient of Friction: Level Surfaces, minimum 0.6.
 - 5. Thickness: 1/8 inch.

6. Size: 12 by 12 inches.
7. Application: All common areas and Living Unit kitchens.

2.4 RESILIENT ACCESSORIES

- A. Rubber Base: Where this designation is indicated, provide rubber wall base complying with FS SS-W-40, Type I and the following:
 1. Products: As follows:
 - a. Armstrong World Industries
 - b. Johnsonite.
 2. Color and Pattern: As selected by Architect from manufacturer's full range of colors and patterns produced for rubber wall base complying with requirements indicated.
 3. Style: Cove with top-set toe.
 4. Minimum Thickness: 1/8 inch.
 5. Height: 4 inches.
 6. Lengths: 120 feet (36.6 m) long.
 7. Outside Corners: Job formed.
 8. Inside Corners: Job formed.
 9. Surface: Smooth.

- B. Rubber Stair Treads and Accessories: Where this designation is indicated, provide rubber stair treads and accessories complying with FS RR-T-650, Composition A and the following:
 1. Available Products: As follows:
 - a. Johnsonite: VIRH Round
 2. Color and Pattern: As selected by Architect from manufacturer's full range of colors and patterns produced for rubber stair treads and accessories complying with requirements indicated.
 3. Static Coefficient of Friction: Step Treads: Minimum 0.8.
 4. Rubber Stair Treads: Type 2 design (designed) products complying with the following requirements:
 - a. Type 2 Design: Raised-disc pattern.
 - b. Abrasive Strips: Provide abrasive strips as specified by product designation indicated above in color selected by Architect from manufacturer's full range of colors.
 - c. Nosing Style: Square, adjustable to cover angles between 60 and 90 degrees.
 - d. Nosing Height: As follows, measured from top of tread to bottom edge of nosing:
 - 1) 1-1/2 inches.
 - e. Thickness: 3/16-inch tapering to 1/8 inch at back edge.
 - f. Size: Lengths and depths to fit each stair tread in one piece or, for treads exceeding maximum lengths manufactured, in equal-length units.
 5. Rubber Risers: Smooth, flat, risers, 1/8 inch thick integral with tread unit.

- C. Vinyl Accessory Molding: Where this designation is indicated, provide vinyl accessory molding complying with the following:
 1. Available Products: As follows:
 - a. Johnsonite.
 2. Color: As selected by Architect from manufacturer's full range of colors produced for vinyl accessory molding complying with requirements indicated.
 3. Transition Strip between VCT and Carpet: CE-XX-A by Johnsonite or approved substitute.

2.5 INSTALLATION ACCESSORIES

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland-cement-based formulation provided or approved by flooring manufacturer for applications indicated.
- B. Stair-Tread-Nose Filler: Two-part epoxy compound recommended by resilient tread manufacturer to fill nosing substrates that do not conform to tread contours.
- C. Adhesives: Water-resistant type recommended by manufacturer to suit resilient products and substrate conditions indicated.
 - 1. Use adhesives that comply with the following limits for VOC content when calculated according to 40 CFR 59, Subpart D (EPA Method 24):
 - a. VCT Adhesives: 50 g/L.
 - b. Cove Base Adhesives: 50 g/L.
- D. Epoxy Adhesives: Two-part epoxy compound recommended by resilient tread manufacturer to adhere rubber treads and risers to substrates.
 - 1. Use adhesives that comply with the following limits for VOC content when calculated according to 40 CFR 59, Subpart D (EPA Method 24):
 - a. Rubber Floor Adhesives: 60 g/L.
- E. Urethane Waterproofing and Tile-Setting Adhesive: Manufacturer's standard proprietary product consisting of 1-part liquid-applied urethane in a consistency suitable for trowel application and intended for use as both waterproofing and tile-setting adhesive in a 2-step process.
 - 1. Product: Hydroment Ultra-Set; Bostik.
 - 2. For use with slip-resistant VCT only.
- F. Seamless-Installation Accessories:
 - 1. Heat-Welding Bead: Manufacturer's solid-strand product for heat welding seams.
 - a. Color: Match floor covering.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions where installation of resilient products will occur, with Installer present, for compliance with requirements for maximum moisture content, alkalinity range, installation tolerances, and other manufacturer's requirements. Verify that substrates and conditions are satisfactory for resilient product installation and comply with requirements specified.
- B. Concrete Subfloors: Verify that concrete slabs comply with ASTM F 710 and the following:
 - 1. Slab substrates are dry and free of curing compounds, sealers, hardeners, and other materials that may interfere with adhesive bond.
 - 2. Verify that adhesion and dryness characteristics have been determined as required in Division 7 Section "Vapor Retarders, Vapor Barriers, and Air Barriers" and meet flooring manufacturer's recommendations.

3. Subfloor finishes comply with requirements specified in Division 3 Section "Cast-in-Place Concrete" for slabs receiving resilient flooring.
 4. Subfloors are free of cracks, ridges, depressions, scale, and foreign deposits.
- C. For wood subfloors, verify the following:
1. Underlayment over subfloor complies with requirements specified in Division 6 Section "Rough Carpentry."
 2. Underlayment surface is free of irregularities and substances that may interfere with adhesive bond, show through surface, or stain flooring.
- D. Do not proceed with installation until unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. General: Comply with resilient product manufacturer's written installation instructions for preparing substrates indicated to receive resilient products.
- B. Use trowelable leveling and patching compounds, according to manufacturer's written instructions, to fill cracks, holes, and depressions in substrates.
- C. Use stair-tread-nose filler, according to resilient tread manufacturer's written instructions, to fill nosing substrates that do not conform to tread contours.
- D. Remove coatings, including curing compounds, and other substances that are incompatible with flooring adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by manufacturer. Do not use solvents.
- E. Broom and vacuum clean substrates to be covered immediately before product installation. After cleaning, examine substrates for moisture, alkaline salts, carbonation, or dust. Do not proceed with installation until unsatisfactory conditions have been corrected.

3.3 TILE INSTALLATION

- A. General: Comply with tile manufacturer's written installation instructions.
- B. Lay out tiles from center marks established with principal walls, discounting minor offsets, so tiles at opposite edges of room are of equal width. Adjust as necessary to avoid using cut widths that equal less than one-half of a tile at perimeter.
1. Lay tiles square with room axis, unless otherwise indicated.
- C. Match tiles for color and pattern by selecting tiles from cartons in the same sequence as manufactured and packaged, if so numbered. Cut tiles neatly around all fixtures. Discard broken, cracked, chipped, or deformed tiles.
1. Lay tiles in basket-weave pattern with grain direction alternating in adjacent tiles.
- D. Scribe, cut, and fit tiles to butt neatly and tightly to vertical surfaces and permanent fixtures, including built-in furniture, cabinets, pipes, outlets, edgings, door frames, thresholds, and nosings.
- E. Extend tiles into toe spaces, door reveals, closets, and similar openings.

- F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on finish flooring as marked on subfloor. Use chalk or other nonpermanent, nonstaining marking device.
- G. Install tiles on covers for telephone and electrical ducts, and similar items in finished floor areas. Maintain overall continuity of color and pattern with pieces of flooring installed on covers. Tightly adhere edges to perimeter of floor around covers and to covers.
- H. Adhere tiles to flooring substrates using a full spread of adhesive applied to substrate to comply with tile manufacturer's written instructions, including those for trowel notching, adhesive mixing, and adhesive open and working times.
 - 1. Provide completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.
- I. Hand roll tiles according to tile manufacturer's written instructions.
- J. Provide waterproofing to set tiles where slip-resistant VCT is indicated on the drawings.

3.4 SHEET FLOORING INSTALLATION

- A. General: Comply with sheet floor covering manufacturer's written installation instructions.
- B. Unroll sheet floor coverings and allow them to stabilize before cutting and fitting, if recommended in writing by manufacturer.
- C. Lay out sheet floor coverings to comply with the following requirements:
 - 1. Maintain uniformity of sheet floor covering direction.
 - 2. Arrange for a minimum number of seams and place them in inconspicuous and low-traffic areas, and not less than 6 inches away from parallel joints in flooring substrates.
 - 3. Match edges of sheet floor coverings for color shading and pattern at seams according to manufacturer's written recommendations.
 - 4. Avoid cross seams.
- D. Scribe, cut, and fit sheet floor coverings to butt neatly and tightly to vertical surfaces and permanent fixtures, including built-in furniture, cabinets, pipes, outlets, edgings, door frames, thresholds, and nosings.
- E. Extend sheet floor coverings into toe spaces, door reveals, closets, and similar openings.
- F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on finish flooring as marked on subfloor. Use chalk or other nonpermanent, nonstaining marking device.
- G. Adhere sheet floor coverings to flooring substrates to comply with floor covering manufacturer's written instructions, including those for trowel notching, adhesive mixing, and adhesive open and working times.
 - 1. Produce completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.
- H. Seamless Installation:

1. Heat-Welded Seams: Comply with ASTM F 1516. Rout joints and use welding bead to permanently fuse sections into a seamless floor covering. Prepare, weld, and finish seams to produce surfaces flush with adjoining floor covering surfaces. Coordinate welding rod with sheet vinyl color and pattern, as available by manufacturer.
- I. Hand roll sheet floor coverings in both directions from center out to embed floor coverings in adhesive and eliminate trapped air. At walls, door casings, and other locations where access by roller is impractical, press floor coverings firmly in place with flat-bladed instrument.

3.5 RESILIENT ACCESSORY INSTALLATION

- A. General: Install resilient accessories according to manufacturer's written installation instructions.
- B. Apply resilient wall base to walls, columns, pilasters, casework and cabinets in toe spaces, locker bases, and other permanent fixtures in rooms and areas where base is required.
1. Install wall base in lengths as long as practicable without gaps at seams and with tops of adjacent pieces aligned.
 2. Tightly adhere wall base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.
 3. Do not stretch base during installation.
 4. On masonry surfaces or other similar irregular substrates, fill voids along top edge of resilient wall base with manufacturer's recommended adhesive filler material.
 5. Form outside corners on job from straight pieces of maximum lengths possible, without whitening at bends. Shave back of base at points where bends occur and remove strips perpendicular to length of base that are only deep enough to produce a snug fit without removing more than half the wall base thickness.
 6. Form inside corners on job, from straight pieces of maximum lengths possible, by cutting an inverted V-shaped notch in toe of wall base at the point where corner is formed. Shave back of base where necessary to produce a snug fit to substrate.
- C. Place resilient accessories so they are butted to adjacent materials and bond to substrates with adhesive. Install reducer strips at edges of flooring that would otherwise be exposed.
1. Locate reducer strips or transition strips to line up centered under doors, unless noted otherwise.
- D. Apply resilient products to stairs as indicated and according to manufacturer's written installation instructions with epoxy adhesive and nose filler.

3.6 CLEANING AND PROTECTING

- A. Perform the following operations immediately after installing resilient products:
1. Remove adhesive and other surface blemishes using cleaner recommended by resilient product manufacturers.
 2. Sweep or vacuum floor thoroughly.
 3. Do not wash floor until after time period recommended by flooring manufacturer.
 4. Damp-mop floor to remove marks and soil.

- B. Clean floor surfaces as soon as possible after installation. Clean products according to manufacturer's written recommendations.
 - 1. After cleaning, apply polish to floor surfaces to provide protective floor finish according to flooring manufacturer's written recommendations. Apply stain resistant sealer under polish as recommended by manufacturer at all areas to receive VCT. Coordinate with Owner's maintenance program.
 - 2. Protect flooring with covers from time of installation to time of polish application per manufacturer's written instructions.

3.7 WASTE MANAGEMENT

- A. Separate waste in accordance with the Waste Management Plan and place in designated areas in the following categories for reuse:
 - 1. Sheet materials larger than 2 square feet.
- B. Close and seal tightly all partly used adhesive containers and store protected in well-ventilated, fire-safe area at moderate temperatures.

END OF SECTION 09 65 00