

Scope of Work

Baxter Academy

54 York St.

Fire Alarm System

Securadyne/Surveillance Specialties will install a new fully addressable Silent Knight fire alarm panel.

We will be installing all new addressable pull stations at each egress location. Smoke Detectors will be installed over the FACP, at the top of each stairwell and over the NAC extender and AES Master Box.

Notification is throughout the entire building using Horn Strobes and Strobes by Gentex.

We will also be installing an AES Master Box (see certification enclosed) application attached.

The system will also be monitored by a Central Station monitoring company.

Pull stations, Smoke Detectors and Sprinkler points will activate the alarm system which will upon alarm notify the Portland Fire Department via the AES Master Box and the Monitoring Company; this will also trigger the evacuation notification throughout the entire building.