LEGEND

99.50	PROP. SPOT ELEVATION
102	PROP. CONTOUR ELEVATION
	PROP. DIRECTION OF SURFACE FLOW
100	EXISTING CONTOUR ELEVATION
F	FILL COVER
V	VAPOR RECOVERY/VENT COVER
TLM	TANK LEVEL MONITOR COVER
B	BRINE/INTERSTITIAL COVER
STP	SUBMERSIBLE TANK PUMP

TANK LEGEND:

4-1 12K REGULAR	EXISTING 12,000 GAL DOUBLE WALL JACKETED STEEL UNDERGROUND STORAGE TANK TO BE ABANDONED IN PLACE. INSTALLED 11/1/1997.
5-1 8K SUPER	EXISTING 8,000 GAL DOUBLE WALL JACKETED STEEL UNDERGROUND STORAGE TANK TO BE ABANDONED IN PLACE. INSTALLED 11/1/1997.
5-2 4K DIESEL	EXISTING 4,000 GAL DOUBLE WALL JACKETED STEEL UNDERGROUND STORAGE TANK TO BE ABANDONED IN PLACE. INSTALLED 11/1/1997.
6-1 15K REGULAR	PROPOSED 15,000 GAL ZCL DOUBLE WALL FRP UNDERGROUND STORAGE TANK
7-1 7-2 8K DIESEL 7K SUPER	PROPOSED 15,000 GAL COMPARTMENTALIZED ZCL DOUBLE WALL FIBERGLASS UNDERGROUND STORAGE TANK BASE=8K DIESEL 7-1 AND END=7K SUPER 7-2

NOTE: DEEP DISPENSER SUMPS ARE REQUIRED AT ISLAND #1 AND #3

NORTH CANOPY PRODUCT PIPING PROFILE (SUPER)

NO SCALE

Copyright © 2016 by MHF Design Consultants, Inc. All Rights Reserved.

F:\Projects\CAD\388015\388OTP.dwg TP 1/26/16 4:15pm DSA

- ☐ SUPERSEDES ALL PREVIOUS ISSUES
- ☐ APPROVED FOR CONSTRUCTION
- ☐ PRELIMINARY-NOT FOR CONSTRUCTION
- ☐ ISSUED TO: _____

DATE _____

Inspection Division Date: 03/03/16

LOCATION MAP
NOT TO SCALE

REV	DATE	BY	REVISION

REVISIONS

MHF Design Consultants, Inc.
44 Stiles Road, Suite One
Salem, New Hampshire 03079
(603) 893-0720
ENGINEERS • PLANNERS • SURVEYORS
www.mhfdesign.com

STATE OF MAINE FRANK C. MONTEIRO 7201 LICENSED PROFESSIONAL ENGINEER 1/26/16

IRVING

DRAWN BY: DSA	DESIGNED BY: FCM
SCALE: 1"=10'	APPROVED BY:
DATE: 1/26/16	PROPERTY NO.:
CAD FILE: 388OTP.DWG PLOTTED:	REF-BLK: REF-BLK: REF-BLK:

IRVING OIL

190 COMMERCE WAY
PORTSMOUTH, NH 03801

PROJECT:
393 COMMERCIAL STREET
PORTLAND, MAINE

SHEET TITLE:
TANK & PIPING PLAN

PROJECT:	DRAWING NO:	REVISION:
	UST2	-

COMPANY SUPERVISOR AND CONTRACTOR TO VERIFY ALL MEASUREMENTS ON WORK OR AT SITE. THIS DRAWING IS THE PROPERTY OF IRVING OIL LTD. AND SHALL BE RETURNED ON COMPLETION OF WORK.