

Portland, Maine



Yes. Life's good here.

Danielle P. West-Chuhta
Corporation Counsel

Michael I. Goldman
Associate Counsel

Anne M. Torregrossa
Associate Counsel

Victoria E. Morales
Associate Counsel

November 4, 2016

NOTICE OF INTENT TO PROSECUTE

To Whom it May Concern,

Please see the attached Notice of Violation and Order to Correct from the City of Portland Fire Prevention Bureau. The Fire Prevention Bureau has referred this matter to me for prosecution in the event that you do not complete and return the required plan of action by the date contained in the Notice of Violation. Your failure to comply will result in the issuance of a summons for you to appear in court, and the imposition of civil penalties in the minimum amount of \$100 per violation per day.

Please contact the Fire Prevention Bureau at (207)874-8400 to resolve these outstanding violations. I look forward to your anticipated cooperation and appreciate your efforts to help keep the citizens of Portland safe.

Sincerely,

A handwritten signature in blue ink that reads 'Anne M. Torregrossa'. The signature is written in a cursive style.

Anne M. Torregrossa
Associate Corporation Counsel
City of Portland

CITY OF PORTLAND
 FIRE PREVENTION BUREAU
 380 Congress Street, Portland, Maine 04101
 fireprevention@portlandmaine.gov
 (207) 874-8400

NOTICE OF VIOLATION AND ORDER TO CORRECT

November 4, 2016

Responsible Party 1: Hilton Stephen 19 Ole Ironside Ln Scarborough, ME 04074		
Location 52 High	CBL 044 A021001	Inspection Date 10/21/2016
Inspector Steven Hall	Inspection Type FP Routine Inspection	Status Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must complete the proposed date of completion column by proposing a reasonable timeframe to remedy each violation. This form must be received by the Fire Prevention Bureau no later than 11/30/2016. The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

YOUR FAILURE TO SUBMIT A PLAN OF ACTION BY THE DATE PROVIDED, OR TO CORRECT ANY VIOLATION WITHIN THE APPLICABLE TIME FRAME, MAY RESULT IN LEGAL ACTION AGAINST YOU, THE IMPOSITION OF CIVIL PENALTIES, AND THE PURSUIT OF OTHER LEGAL REMEDIES.

Violation	Proposed Date of Completion
NFPA 101-7.2.4.3.1 FIRE BARRIER REQUIRES MAINTENANCE; Fire barriers separating buildings or areas between which there are horizontal exits shall have a minimum 2-hour fire resistance rating, unless otherwise provided in 7.2.4.4.1, and shall provide a separation that is continuous to the finished grounded level. Hole in the third floor stairwell/apartment door assembly	
NFPA 10- 7.2.4.4 FIRE EXTINGUISHER INSPECTION TAG; Where manual inspections are conducted, records for manual inspections shall be kept on a tag or label attached to the fire extinguisher, on an inspection checklist maintained on file, or by an electronic method. Need service test on Extinguisher	___/___/___
NFPA 101- 31.3.4.5.1 SMOKE ALARMS REQUIRED; In buildings other than those equipped through out with an existing, complete automatic smoke detection system, smoke alarms shall be installed in accordance with 9.6.2.10, as modified by 31.3.4.5.2, outside every sleeping area in the immediate vicinity of the bedrooms and on all levels of the dwelling unit, including basements. Smoke alarms missing in front stairwell	IMMEDIATELY install temporary alarms where required. Your signature below indicates that temporary alarms have already been installed.
NFPA 70 MISSING BREAKER IN PANEL; Refer to NFPA 70, National Electrical Code, for information on missing breakers in an electrical panel. Need filler	___/___/___
NFPA 101- 31.3.2.1.1 BOILER PROTECTION REQUIRED; The areas described in Table 31.3.2.1.1 shall be protected as indicated: Boiler and fuel-fired heater rooms serving more than a single dwelling unit (minimum separation/protection is 1 hour or sprinklers) Need sprinkler head over boiler	___/___/___

Violation	Proposed Date of Completion
<p>NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED; Refer to NFPA 101- Table 8.3.4.2 that states fire door assemblies for vertical shafts (including stairways, exits, and refuse chutes) are rated and required for 1 hour.</p> <p>Need fire doors</p>	<p>___ / ___ / ___</p>
<p>NFPA 80- ANNEX D.4 1-HOUR FIRE DOORS ASSEMBLIES REQ; Listings are provided for floor fire door assemblies that are installed in fire-rated floor-ceiling or roof-ceiling assemblies that have been tested in accordance with the methods described in NFPA 288. The listing indicates the fire-rated assembly and the hourly rating (3 hours, 2 hours, 1.5 hours, 1 hour, .75 hours) for which the door can be permitted to be used so that access to the space above the ceiling or to the floor above can be provided without adversely affecting the fire resistance rating of the entire assembly. The listing provides limitations on the maximum size of an individual door opening and the total area of all door openings permitted for each 100 square feet of floor or ceiling.</p> <p>1-HOUR FIRE DOORS ASSEMBLIES REQUIRED</p>	<p>___ / ___ / ___</p>
<p>NFPA 54- 9.6.4 UTILITY DISCONNECTS BLOCKED; Each appliance connected to a piping system shall have an accessible, approved manual shutoff valve with a nondisplaceable valve member, or a listed gas convenience outlet. Appliance shutoff valves and convenience outlets shall serve a single appliance only and shall be installed in accordance with 9.6.4.1.</p> <p>Utility disconnects blocked</p>	<p>___ / ___ / ___</p>
<p>NFPA 101- 7.9.1.1 EMERGENCY LIGHTING REQUIRED; Emergency lighting facilities for means of egress shall be provided in accordance with Section 7.9 for the following: (1) Buildings or structures where required in Chapters 11 through 43 (2) Underground and limited access structures as addressed in Section 11.7 (3) High-rise buildings as required by other sections of this code (4) Doors equipped with delayed-egress locks (5) Stair shaft and vestibule of smokeproof enclosures, for which of the following also apply: (a) The stair shaft and vestibule shall be permitted to include a standby generator that is installed for the smokeproof enclosure mechanical ventilation equipment (b) The standby generator shall be permitted to be used for the stair shaft and vestibule emergency lighting power supply (6) New access-controlled egress doors in accordance with 7.2.1.6.2</p> <p>EMERGENCY LIGHTING FACILITIES FOR MEANS OF EGRESS SHALL BE PROVIDED IN ACCORDANCE WITH NFPA 1 LIFE SAFETY CODE. 2009 Chp. 14.13.1 and NFPA 101 2009 Chp. 4.6.13.1</p>	<p>___ / ___ / ___</p>

VIOLATOR CERTIFICATION

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau’s discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.

Date

Responsible Party

Date

Responsible Party

SEEN AND AGREED

Date

Fire Prevention Bureau