

Portland, Maine



Yes. Life's good here.

Danielle P. West-Chuhta
Corporation Counsel

Michael I. Goldman
Associate Counsel

Anne M. Torregrossa
Associate Counsel

Victoria E. Morales
Associate Counsel

November 29, 2016

NOTICE OF INTENT TO PROSECUTE

To Whom it May Concern,

Please see the attached Notice of Violation and Order to Correct from the City of Portland Fire Prevention Bureau. The Fire Prevention Bureau has referred this matter to me for prosecution in the event that you do not complete and return the required plan of action by the date contained in the Notice of Violation. Your failure to comply will result in the issuance of a summons for you to appear in court, and the imposition of civil penalties in the minimum amount of \$100 per violation per day.

Please contact the Fire Prevention Bureau at (207)874-8400 to resolve these outstanding violations. I look forward to your anticipated cooperation and appreciate your efforts to help keep the citizens of Portland safe.

Sincerely,

A handwritten signature in blue ink that reads 'Anne M. Torregrossa'. The signature is written in a cursive style.

Anne M. Torregrossa
Associate Corporation Counsel
City of Portland

CITY OF PORTLAND
 FIRE PREVENTION BUREAU
 380 Congress Street, Portland, Maine 04101
 fireprevention@portlandmaine.gov
 (207) 874-8400

NOTICE OF VIOLATION AND ORDER TO CORRECT

November 29, 2016

| | | |
|--|---|------------------------------------|
| Responsible Party 1: Coyne Margaret 51 woodfield rd Portland, ME 04102 | | |
| Location 92 Danforth | CBL 044 A022001 | Inspection Date 7/1/2016 |
| Inspector Steven Hall | Inspection Type FP Routine Inspection | Status Failed |

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must complete the proposed date of completion column by proposing a reasonable timeframe to remedy each violation. This form must be received by the Fire Prevention Bureau no later than 12/15/2016. The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

YOUR FAILURE TO SUBMIT A PLAN OF ACTION BY THE DATE PROVIDED, OR TO CORRECT ANY VIOLATION WITHIN THE APPLICABLE TIME FRAME, MAY RESULT IN LEGAL ACTION AGAINST YOU, THE IMPOSITION OF CIVIL PENALTIES, AND THE PURSUIT OF OTHER LEGAL REMEDIES.

| Violation | Proposed Date of Completion |
|--|------------------------------------|
| NFPA 101- 7.2.1.15.8 FIRE DOOR ASSEMBLY REQ REPAIR; Door openings not in proper operating condition shall be repaired or replaced without delay. Hallway fire doors not self closing | ___/___/___ |
| NFPA 101-7.9.3 EMERGENCY LIGHTS REQUIRE MAINTENANCE; 7.9.3 Periodic Testing of Emergency Equipment 7.9.3.1 Required emergency lighting systems shall be tested in accordance with one of the three options offered by 7.9.3.1.1, 7.9.3.1.2, or 7.9.3.1.3. 7.9.3.1.1 Testing of required emergency lighting systems shall be permitted to be conducted as follows: (1) Functional testing shall be conducted monthly with a minimum of 3 weeks and a maximum of 5 weeks between tests, for not less than 30 seconds, except as otherwise permitted by 7.9.3.1.1(2). (2) The test interval shall be permitted to be extended beyond 30 days with the approval of the authority having jurisdiction. (3) Functional testing shall be conducted annually for a minimum 1-1/2 hours if the emergency lighting system is battery powered. (4) The emergency lighting equipment shall be fully operational for the duration of the test required by 7.9.3.1.1(1) and (3). (5) Written records of visual inspections and tests shall be kept by the owner for inspection by the authority having jurisdiction. 1st and second hallways not working | ___/___/___ |
| NFPA 10- 7.2.4.4 FIRE EXTINGUISHER INSPECTION TAG; Where manual inspections are conducted, records for manual inspections shall be kept on a tag or label attached to the fire extinguisher, on an inspection checklist maintained on file, or by an electronic method. Extinguisher in laundry area needs service tag | ___/___/___ |

| Violation | Proposed Date of Completion |
|--|-----------------------------|
| NFPA 101- 31.3.2.1.1 BOILER PROTECTION REQUIRED; The areas described in Table 31.3.2.1.1 shall be protected as indicated: Boiler and fuel-fired heater rooms serving more than a single dwelling unit (minimum separation/protection is 1 hour or sprinklers) No boiler protection or over water heaters | ____ / ____ / ____ |
| NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED; Refer to NFPA 101- Table 8.3.4.2 that states fire door assemblies for vertical shafts (including stairways, exits, and refuse chutes) are rated and required for 1 hour. Fire door to the basement missing a door | ____ / ____ / ____ |

VIOLATOR CERTIFICATION

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau’s discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.

 Date Responsible Party

 Date Responsible Party

SEEN AND AGREED

 Date Fire Prevention Bureau