

Portland, Maine



Yes. Life's good here.

Danielle P. West-Chuhta
Corporation Counsel

Anne M. Torregrossa
Associate Counsel

Michael I. Goldman
Associate Counsel

July 14, 2016

NOTICE OF INTENT TO PROSECUTE

CMK, LLC
51 Woodfield Road
Portland, Maine 04102

CMK, LLC
c/o C. Alan Beagle
P.O. Box 7044
Portland, Maine 04112-7044

RE: 92 Danforth Street
CBL044 A022001

To Whom it May Concern,

Please see the attached Inspection Violations. The City of Portland Fire Department has referred this matter to me for prosecution. In order to avoid prosecution, you must submit to Fire Prevention Bureau a plan of action to remedy the violations no later than **July 29, 2016**.

**YOUR FAILURE TO SUBMIT A PLAN OF ACTION
WITHIN THE TIMEFRAME PROVIDED WILL RESULT IN
LEGAL ACTION AND THE IMPOSITION OF CIVIL PENALTIES.**

Please feel free to contact Tori Ross of the Fire Prevention Bureau at (207)874-8400 with any questions. I look forward to your anticipated cooperation and appreciate your efforts to help keep the citizens of Portland safe.

Sincerely,

Anne M. Torregrossa
Associate Corporation Counsel
City of Portland

**CITY OF PORTLAND
PORTLAND FIRE DEPARTMENT**

380 Congress Street
Portland, Maine 04101 # 353914

Inspection Violations

Owner/Manager Cmk Llc		Inspector Steven Hall	Inspection Date 7/1/2016
Location 92 Danforth	CBL 044 A022001	Status Failed	Inspection Type Fire Company-FP Routine Inspec

Code	Int/Ext	Floor	Unit No.	Area	Compliance Date
------	---------	-------	----------	------	-----------------

1) 73.05

Violation: NFPA 101- 7.2.1.15.8 FIRE DOOR ASSEMBLY REQ REPAIR; DOOR OPENINGS NOT IN PROPER OPERATING CONDITION SHALL BE REPAIRED OR REPLACED WITHOUT DELAY.

Notes: HALLWAY FIRE DOORS NOT SELF CLOSING

2) 80.16

Violation: NFPA 101-7.9.3 EMERGENCY LIGHTS REQUIRE MAINTENANCE; 7.9.3 Periodic Testing of Emergency Equipment

7.9.3.1 Required emergency lighting systems shall be tested in accordance with one of the three options offered by 7.9.3.1.1, 7.9.3.1.2, or 7.9.3.1.3.

7.9.3.1.1 Testing of required emergency lighting systems shall be permitted to be conducted as follows:

(1) Functional testing shall be conducted monthly with a minimum of 3 weeks and a maximum of 5 weeks between tests, for not less than 30 seconds, except as otherwise permitted by 7.9.3.1.1(2).

(2) The test interval shall be permitted to be extended beyond 30 days with the approval of the authority having jurisdiction.

(3) Functional testing shall be conducted annually for a minimum 1-1/2 hours if the emergency lighting system is battery powered.

(4) The emergency lighting equipment shall be fully operational for the duration of the test required by 7.9.3.1.1(1) and (3).

(5) Written records of visual inspections and tests shall be kept by the owner for inspection by the authority having jurisdiction.

Notes: 1ST AND SECOND HALLWAYS NOT WORKING

3) 81.20

Violation: NFPA 10- 7.2.4.4 FIRE EXTINGUISHER INSPECTION TAG; Where manual inspections are conducted, records for manual inspections shall be kept on a tag or label attached to the fire extinguisher, on an inspection checklist maintained on file, or by an electronic method.

Notes: EXTINGUISHER IN LAUNDRY AREA NEEDS SERVICE TAG

4) 3.011

Violation: NFPA 101- 31.3.2.1.1 BOILER PROTECTION REQUIRED; THE AREAS DESCRIBED IN TABLE 31.3.2.1.1 SHALL BE PROTECTED AS INDICATED:
BOILER AND FUEL-FIRED HEATER ROOMS SERVING MORE THAN A SINGLE DWELLING UNIT (MINIMUM SEPARATION/PROTECTION IS 1 HOUR OR SPRINKLERS)

Notes: NO BOILER PROTECTION OR OVER WATER HEATERS

**CITY OF PORTLAND
PORTLAND FIRE DEPARTMENT**

380 Congress Street
Portland, Maine 04101

Inspection Violations

Owner/Manager Cmk Lic		Inspector Steven Hall	Inspection Date 7/1/2016
Location 92 Danforth	CBL 044 A022001	Status Failed	Inspection Type Fire Company-FP Routine Inspec

5) 80.37

Violation: NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED; REFER TO NFPA 101- TABLE 8.3.4.2 THAT STATES FIRE DOOR ASSEMBLIES FOR VERTICAL SHAFTS (INCLUDING STAIRWAYS, EXITS, AND REFUSE CHUTES) ARE RATED AND REQUIRED FOR 1 HOUR.

Notes: FIRE DOOR TO THE BASEMENT MISSING A DOOR

Comments: