

Portland, Maine



Yes. Life's good here.

Danielle P. West-Chuhta
Corporation Counsel

Michael I. Goldman
Associate Counsel

Anne M. Torregrossa
Associate Counsel

Victoria E. Morales
Associate Counsel

December 2, 2016

NOTICE OF INTENT TO PROSECUTE

To Whom it May Concern,

Please see the attached Notice of Violation and Order to Correct from the City of Portland Fire Prevention Bureau. The Fire Prevention Bureau has referred this matter to me for prosecution in the event that you do not complete and return the required plan of action by the date contained in the Notice of Violation. Your failure to comply will result in the issuance of a summons for you to appear in court, and the imposition of civil penalties in the minimum amount of \$100 per violation per day.

Please contact the Fire Prevention Bureau at (207)874-8400 to resolve these outstanding violations. I look forward to your anticipated cooperation and appreciate your efforts to help keep the citizens of Portland safe.

Sincerely,

A handwritten signature in blue ink that reads 'Anne M. Torregrossa'. The signature is written in a cursive style.

Anne M. Torregrossa
Associate Corporation Counsel
City of Portland

CITY OF PORTLAND
 FIRE PREVENTION BUREAU
 380 Congress Street, Portland, Maine 04101
 fireprevention@portlandmaine.gov
 (207) 874-8400

NOTICE OF VIOLATION AND ORDER TO CORRECT

December 2, 2016

Responsible Party 1: Plummer Joanne 94 WOODFORD ST PORTLAND, ME 04103		
Location 94 WOODFORD ST	CBL 125 N023001	Inspection Date 11/27/2016
Inspector Brad James	Inspection Type FP Routine Inspection	Status Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must complete the proposed date of completion column by proposing a reasonable timeframe to remedy each violation. This form must be received by the Fire Prevention Bureau no later than 12/30/2016. The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

YOUR FAILURE TO SUBMIT A PLAN OF ACTION BY THE DATE PROVIDED, OR TO CORRECT ANY VIOLATION WITHIN THE APPLICABLE TIME FRAME, MAY RESULT IN LEGAL ACTION AGAINST YOU, THE IMPOSITION OF CIVIL PENALTIES, AND THE PURSUIT OF OTHER LEGAL REMEDIES.

Violation	Proposed Date of Completion
NFPA 101- 31.3.1.1.1 VERTICAL OPENINGS NOT FIRE RATED; Vertical openings shall be enclosed or protected in accordance with Section 8.6. Front hall 1st floor.	___/___/___
NFPA 101- 31.3.7 FLOOR/ CEILINGS ASSEMBLY NOT SMOKE-TIGHT; In buildings other than those meeting the requirements of 31.3.7.1, 31.3.7.2, 31.3.7.3, 31.3.7.4, or 31.3.7.5, in addition to the following criteria to be met. Front hall 1st floor.	___/___/___
NFPA 101- 7.5.1.1 EXIT OBSTRUCTED; Where exits are not immediately accessible from an open floor area, continuous passageways, aisles, or corridors leading directly to every exit shall be maintained and shall be arranged to provide access for each occupant to not less than two exits by separate ways of travel, unless otherwise provided in 7.5.1.1.3 and 7.5.1.1.4. Basement/1st floor hallway rear.	IMMEDIATELY remove all obstructions from the exits. Your signature below indicates that all obstructions have been removed and will not be replaced.
NFPA 101- 7.2.1.8.1 FIRE DOORS MUST BE SELF- OR AUTO-CLOSING; A door leaf normally required to be kept closed shall not be secured in the open position at any time and shall be self-closing or automatic-closing in accordance with 7.2.1.8.2, unless otherwise permitted by 7.2.1.8.3. All fire doors.	___/___/___

Violation	Proposed Date of Completion
<p>NFPA 720- 5.5.6.1 CO ALARMS REQUIRED; The performance, location, and mounting of notification appliances used to initiate or direct action, evacuation or relocation of the occupants, or for providing information to occupants or staff, shall comply with the requirements of Chapter 6. All apartments and basement.</p>	<p>IMMEDIATELY install temporary alarms where required. Your signature below indicates that temporary alarms have already been installed.</p>
<p>NFPA 101- 31.3.4.5.1 SMOKE ALARMS REQUIRED; In buildings other than those equipped through out with an existing, complete automatic smoke detection system, smoke alarms shall be installed in accordance with 9.6.2.10, as modified by 31.3.4.5.2, outside every sleeping area in the immediate vicinity of the bedrooms and on all levels of the dwelling unit, including basements. All apartments and basement.</p>	<p>IMMEDIATELY install temporary alarms where required. Your signature below indicates that temporary alarms have already been installed.</p>
<p>NFPA 1 EXCESSIVE/DISORDERLY STORAGE; Reference NFPA 1 for excessive fuel-load. Clean up debris in basement.</p>	<p>___/___/___</p>
<p>NFPA 70- ARTICLE 110.12 B EXPOSED WIRING CONNECTIONS; Internal parts of electrical equipment, including busbars, wiring terminals, insulators, and other surfaces, shall not be damaged or contaminated by foreign materials such as paint, plaster, cleaners, abrasives, or corrosive residues. There shall be no damaged parts that may adversely affect safe operation or mechanical strength of the equipment such as parts that are broken; bent; cut; or deteriorated by corrosion, chemical reaction, or overheating. Basement at bottom of stairwell.</p>	<p>___/___/___</p>
<p>NFPA 70- 590.6 EXTENSION CORDS; Ground-fault protection for personnel for all temporary wiring installations shall be provided to comply with 590.6(A) and (B). This section shall apply only to temporary wiring installations used to supply temporary power to equipment used by personnel during construction, remodeling, maintenance, repair, or demolition of buildings, structures, equipment, or similar activities. Run from Apt 1 rear to freezer on delta side deck 1st floor.</p>	<p>___/___/___</p>
<p>NFPA 70 MISSING BOX COVERS; Refer to NFPA 70, National Electrical Code, on standards for missing box covers. Front hallway 1st floor.</p>	<p>___/___/___</p>
<p>NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED; Refer to NFPA 101- Table 8.3.4.2 that states fire door assemblies for vertical shafts (including stairways, exits, and refuse chutes) are rated and required for 1 hour. All apartment and basement doors</p>	<p>___/___/___</p>
<p>NFPA 1- 14.6.3 COMBUSTIBLES STORED UNDER STAIRWAY; Enclosed, usable spaces, within exit enclosures shall be prohibited, including under stairs, unless otherwise permitted by 14.6.3.2. 1st floor front hallway has excessive storage and a washer/dryer hook up under stairwell.</p>	

VIOLATOR CERTIFICATION

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau’s discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.

Date

Responsible Party

Date

Responsible Party

SEEN AND AGREED

Date

Fire Prevention Bureau