

COMMENTS

10/13/00 Pre-Con by phone - ? on handrail - "Must have" ok, will comply.  
? on exceeding footprint referred to M.S. (P)

See Contractor's description of work on his application for details (P)

10/17/00 - Front Right bsmt entrance framed on existing foundation - ok to close  
in - appears to be done per plans. +M (2 other projects not started)

Inspection Record

Type	Date
Foundation: _____	_____
Framing: _____	_____
Plumbing: _____	_____
Final: _____	_____
Other: _____	_____

## BUILDING PERMIT REPORT

DATE: 05 OCT. 2000 ADDRESS: 10 Stratton St. CBL: 044-0-001

REASON FOR PERMIT: Replace stairs

BUILDING OWNER: Kathleen Brown

PERMIT APPLICANT: CONTRACTOR Brad Baker

USE GROUP: R-3 CONSTRUCTION TYPE: 50 CONSTRUCTION COST: 5,000.00 PERMIT FEES: \$54.00

The City's Adopted Building Code (The BOCA National Building Code/1999 with City Amendments)  
The City's Adopted Mechanical Code (The BOCA National Mechanical Code/1993)

### CONDITION(S) OF APPROVAL

This permit is being issued with the understanding that the following conditions shall be met: \*1, \*11, \*13 \*32


1. This permit does not excuse the applicant from meeting applicable State and Federal rules and laws.
2. Before concrete for foundation is placed, approvals from the Development Review Coordinator and Inspection Services must be obtained. (A 24 hour notice is required prior to inspection) "**ALL LOT LINES SHALL BE CLEARLY MARKED BEFORE CALLING.**"
3. Foundation drain shall be placed around the perimeter of a foundation that consists of gravel or crushed stone containing not more than 10 percent material that passes through a No. 4 sieve. The drain shall extend a minimum of 12 inches beyond the outside edge of the footing. The thickness shall be such that the bottom of the drain is not higher than the bottom of the base under the floor, and that the top of the drain is not less than 6 inches above the top of the footing. The top of the drain shall be covered with an approved filter membrane material. Where a drain tile or perforated pipe is used, the invert of the pipe or tile shall not be higher than the floor elevation. The top of joints or top of perforations shall be protected with an approved filter membrane material. The pipe or tile shall be placed on not less than 2" of gravel or crushed stone, and shall be covered with not less than 6" of the same material. Section 1813.5.2
4. Foundations anchors shall be a minimum of 1/2" in diameter, 7" into the foundation wall, minimum of 12" from corners of foundation and a maximum 6' O.C. between bolts. Section 2305.17
5. Waterproofing and dampproofing shall be done in accordance with Section 1813.0 of the building code.
6. Precaution must be taken to protect concrete from freezing. Section 1908.0
7. It is strongly recommended that a registered land surveyor check all foundation forms before concrete is placed. This is done to verify that the proper setbacks are maintained.
8. Private garages located beneath habitable rooms in occupancies in Use Group R-1, R-2, R-3 or I-1 shall be separated from adjacent interior spaces by fire partitions and floor/ceiling assembly which are constructed with not less than 1-hour fire resisting rating. Private garages attached side-by-side to rooms in the above occupancies shall be completely separated from the interior spaces and the attic area by means of 1/2 inch gypsum board or the equivalent applied to the garage side. (Chapter 4, Section 407.0 of the BOCA/1999)
9. All chimneys and vents shall be installed and maintained as per Chapter 12 of the City's Mechanical Code. (The BOCA National Mechanical Code/1993). Chapter 12 & NFPA 211
10. Sound transmission control in residential building shall be done in accordance with Chapter 12, Section 1214.0 of the City's Building Code.
11. Guardrails & Handrails: A guardrail system is a system of building components located near the open sides of elevated walking surfaces for the purpose of minimizing the possibility of an accidental fall from the walking surface to the lower level. Minimum height all Use Groups 42". In occupancies in Use Group A, B, H-4, I-1, I-2, M, R, public garages and open parking structures, open guards shall have balusters or be of solid material such that a sphere with a diameter of 4" cannot pass through any opening. Guards shall not have an ornamental pattern that would provide a ladder effect. Handrails shall be a minimum of 34" but not more than 38". Exception: Handrails that form part of a guard shall have a height not less than 36 inches (914 mm) and not more than 42 inches (1067 mm). Handrail grip size shall have a circular cross section with an outside diameter of at least 1 1/4" and not greater than 2". (Sections 1021 & 1022.0). Handrails shall be on both sides of stairway. (Section 1014.7)
12. Headroom in habitable space is a minimum of 7'6". (Section 1204.0)
13. Stair construction in Use Group R-3 & R-4 is a minimum of 10" tread and 7 1/2" maximum rise. All other Use Group minimum 11" tread, 7" maximum rise. (Section 1014.0)
14. The minimum headroom in all parts of a stairway shall not be less than 80 inches. (6'8") 1014.4
15. Every sleeping room below the fourth story in buildings of Use Groups R and I-1 shall have at least one operable window or exterior door approved for emergency egress or rescue. The units must be operable from the inside without the use of special knowledge or separate tools. Where windows are provided as means of egress or rescue they shall have a sill height not more than 44 inches (1118mm) above the floor. All egress or rescue windows from sleeping rooms shall have a minimum net clear opening height dimension of 24 inches (610mm). The minimum net clear opening width dimension shall be 20 inches (508)mm, and a minimum net clear opening of 5.7 sq. ft. (Section 1010.4)
16. Each apartment shall have access to two (2) separate, remote and approved means of egress. A single exit is acceptable when it exits directly from the apartment to the building exterior with no communications to other apartment units. (Section 1010.1)
17. All vertical openings shall be enclosed with construction having a fire rating of at least one (1) hour, including fire doors with self closure's. (Over 3 stories in height requirements for fire rating is two (2) hours. (Section 710.0)
18. The boiler shall be protected by enclosing with (1) hour fire rated construction including fire doors and ceiling, or by providing automatic extinguishment. (Table 302.1.1)

19. All single and multiple station smoke detectors shall be of an approved type and shall be installed in accordance with the provisions of the City's Building Code Chapter 9, Section 920.3.2 (BOCA National Building Code/1999), and NFPA 101 Chapter 18 & 19. (Smoke detectors shall be installed and maintained at the following locations):

- In the immediate vicinity of bedrooms
- In all bedrooms
- In each story within a dwelling unit, including basements

20. A portable fire extinguisher shall be located as per NFPA #10. They shall bear the label of an approved agency and be of an approved type. (Section 921.0)
21. The Fire Alarm System shall be installed and maintained to NFPA #72 Standard.
22. The Sprinkler System shall be installed and maintained to NFPA #13 Standard.
23. All exit signs, lights and means of egress lighting shall be done in accordance with Chapter 10 Section & Subsections 1023.0 & 1024.0 of the City's Building Code. (The BOCA National Building Code/1999)
24. Section 25 - 135 of the Municipal Code for the City of Portland states, "No person or utility shall be granted a permit to excavate or open any street or sidewalk from the time of November 15 of each year to April 15 of the following year".
25. The builder of a facility to which Section 4594-C of the Maine State Human Rights Act Title 5 MRSA refers, shall obtain a certification from a design professional that the plans commencing construction of the facility, the builder shall submit the certification the Division of Inspection Services.
26. Ventilation and access shall meet the requirements of Chapter 12 Sections 1210.0 and 1211.0 of the City's Building Code. (Crawl spaces & attics).
27. All electrical, plumbing and HVAC permits must be obtained by Master Licensed holders of their trade. No closing in of walls until all electrical (min. 72 hours notice) and plumbing inspections have been done.
28. All requirements must be met before a final Certificate of Occupancy is issued.
29. All building elements shall meet the fastening schedule as per Table 2305.2 of the City's Building Code (The BOCA National Building Code/1996).
30. Ventilation of spaces within a building shall be done in accordance with the City's Mechanical code (The BOCA National Mechanical Code/1993). (Chapter M-16)
31. Please read and implement the attached Land Use Zoning report requirements. *Not to increase the foot print of the existing steps*
32. Boring, cutting and notching shall be done in accordance with Sections 2305.3, 2305.3.1, 2305.4.4 and 2305.5.1 of the City's Building Code.
33. Bridging shall comply with Section 2305.16.
34. Glass and glazing shall meet the requirements of Chapter 24 of the building code. (Safety Glazing Section 2406.0)
35. All signage, shall be done in accordance with Section 3102.0 signs of the City's Building Code, (The BOCA National Building Code/1999).
36. All flashing shall comply with Section 1406.3.10.

\*37. See attachment.

  
Lt. McDougall, PFD  
Marge Schmuckal, Zoning Administrator

PSH 10/1/00

\*\*This permit is herewith issued, on the basis of plans submitted and conditions placed on these plans, any deviations shall require a separate approval.

\*\*\*THIS PERMIT HAS BEEN ISSUED WITH THE UNDERSTANDING THAT ALL THE CONDITIONS OF THE APPROVAL SHALL BE COMPLETED. THEREFORE, BEFORE THE WORK IS COMPLETED A REVISED PLAN OR STATEMENT FROM THE PERMIT HOLDER SHALL BE SUBMITTED TO THIS OFFICE SHOWING OR EXPLAINING THAT THE CONDITIONS HAVE BEEN MET. IF THIS REQUIREMENT IS NOT RECEIVED YOUR CERTIFICATE OF OCCUPANCY SHALL BE WITHHELD.

\*\*\*\*ALL PLANS THAT REQUIRE A PROFESSIONAL DESIGNER'S SEAL, (AS PER SECTION 114.0 OF THE BUILDING CODE) SHALL ALSO BE PRESENTED TO THIS DIVISION ON AUTO CAD LT. 2000, DXF FORMAT OR EQUIVALENT.

\*\*\*\*\*CERTIFICATE OF OCCUPANCY FEE \$50.00

**THIS IS NOT A PERMIT/CONSTRUCTION CANNOT COMMENCE UNTIL THE PERMIT IS ISSUED**

**Building or Use Permit Pre-Application  
Additions/Alterations/Accessory Structures  
To Detached Single Family Dwelling**

In the interest of processing your application in the quickest possible manner, please complete the information below for a Building or Use Permit.

**NOTE\*\*** If you or the property owner owes real estate or personal property taxes or user charges on any property within the City, payment arrangements must be made before permits of any kind are accepted.

Location/Address of Construction: 10 STRATTON STREET PORTLAND, ME, 04101

Tax Assessor's Chart, Block & Lot Number Chart# <u>044</u> Block# <u>070</u> Lot# <u>091</u>		Owner: <u>KATHLEEN E. BROWN</u>	Telephone#:
Owner's Address: <u>KATHLEEN E. BROWN c/o BRAD BARKER RR1 Box 3910 Leeds, Me. 04263</u>		Lessee/Buyer's Name (If Applicable)	Cost Of Work: <u>\$5,000.00</u> Fee <u>\$54.00</u>
Proposed Project Description: (Please be as specific as possible) <u>#1 Replace Back Steps - Building with Pressure Treated</u> <u>TURNING PARALLEL TO #9 UNIT TO STAY AWAY FROM PROPERTY LINE + MEET BUILDING CODES. #2 PROJECT,</u> <u>Replace Side Steps with P.T. Project #1 Replace cellar roof + Building stairs - TRIM + CLAPBOARD REPAIR ON EXTERIOR</u> <u>MINOR FOUNDATION WORK,</u> <u>REPAIR OR REPLACE EXT. DOORS</u>			
Contractor's Name, Address & Telephone No. <u>Leeds Building Supply - BRAD BARKER</u> Recd By: <u>(Signature)</u> <u>P.O. Box 226 - Leeds, Me. 04263 - 207-524-3301</u>			

Separate permits are required for Internal & External Plumbing, HVAC and Electrical installation.

- All construction must be conducted in compliance with the 1996 B.O.C.A. Building Code as amended by Section 6-Art II.
- All plumbing must be conducted in compliance with the State of Maine Plumbing Code.
- All Electrical Installation must comply with the 1996 National Electrical Code as amended by Section 6-Art III.
- HVAC (Heating, Ventilation and Air Conditioning) installation must comply with the 1993 BOCA Mechanical Code.

You must include the following with you application:

- 1) A Copy of Your Deed or Purchase and Sale Agreement
- 2) A Copy of your Construction Contract, if available
- 3) A Plot Plan (Sample Attached)

If there is expansion to the structure, a complete plot plan (Site Plan) must include:

The shape and dimension of the lot, all existing buildings (if any), the proposed structure and the distance from the actual property lines. Structures include decks porches, a bow windows cantilever sections and roof overhangs, as well as, sheds, pools, garages and any other accessory structures.  
Scale and required zoning district setbacks

**4) Building Plans (Sample Attached)**

A complete set of construction drawings showing all of the following elements of construction:

- Cross Sections w/Framing details (including porches, decks w/ railings, and accessory structures)
- Floor Plans & Elevations
- Window and door schedules
- Foundation plans with required drainage and dampproofing
- Electrical and plumbing layout. Mechanical drawings for any specialized equipment such as furnaces, chimneys, gas equipment, HVAC equipment (air handling) or other types of work that may require special review must be included.

**Certification**

I hereby certify that I am the Owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his/her authorized agent. I agree to conform to all applicable laws in my jurisdiction. In addition, if a permit for work described in this application is issued, I certify that the Code Official's authorized representative shall have the authority to enter all areas covered by this permit at any reasonable hour to enforce the provisions of the laws applicable to this permit.

Signature of applicant: (Signature) Date: 9/22/00

Building Permit Fee: \$30.00 for the 1st \$1000. cost plus \$6.00 per \$1,000.00 construction cost thereafter.

KEEP THIS PORTION

**REAL ESTATE PROPERTY TAX STATEMENT**  
City of Portland

**2001**  
Fiscal Year  
**July 1, 2000 - June 30, 2001**  
Owner of Record as of April 1, 2000

**BROWN KATHLEEN E**  
**10 STRATTON ST**  
**PORTLAND, ME 04101**



ACCOUNT NUMBER  
**000006446**

CBL  
**044 - B-040-001**

LENDING INST.

Assessed Property Description  
**44-B-40**  
**STRATTON ST 22**  
**CALLED 10**  
**2128 SF**

*Ch # 1719*  
*9/12/00*  
*1,744.80*

**CURRENT BILLING DISTRIBUTION**

School	\$1,835.53
Public Works	\$191.93
Parks & Recreation	\$122.14
Fire	\$258.23
Police	\$268.70
Debt Repayments	\$394.32
General Government	\$170.99
County	\$101.20
Health & Human Services	(\$73.26)
Library	\$111.67
Metro Transit District	\$76.77
Enterprise Funds	(\$31.41)
Regional Waste Systems	\$62.81

**CURRENT BILLING INFORMATION**

Land Value	\$28,900.00
Building Value	\$123,500.00
Total Value	\$152,400.00
Exemptions	\$0.00
Homestead	\$7,000.00
Taxable Value	\$145,400.00
Tax Rate	24.00
<b>TOTAL TAX</b>	<b>\$3,489.60</b>
<b>AMOUNT PAID</b>	<b>\$0.00</b>

**Remittance Instructions**

To avoid standing in line, it is recommended that taxes be paid by mail. Please make check or money order payable to: **CITY OF PORTLAND**. Credit cards are not accepted for property tax payments.

Use enclosed envelope to mail in your payment.

Please be sure remittance address on back side of **RETURN** portion of this tax bill is clearly visible through the window in the return envelope.

Use top right margin for change of address.

# ANDROSCOGGIN TITLE COMPANY

95 Main Street, P.O. Box 867  
Auburn, ME 04212-0867  
(207) 784-6413 Fax (207) 784-4361

95 Congress Street, P.O. Drawer L  
Rumford, ME 04276-2016  
(207) 369-9032 Fax (207) 369-9421

July 14, 2000

Jill Checkoway, Esq.  
Skelton, Taintor & Abbott  
95 Main Street  
Auburn, ME 04212

RE: Kathleen Brown  
10 Stratton Place, Portland, Maine  
Lot 40, Tax Map 44-B

Dear Jill:


In response to your recent request, we have updated the title to the above premises from August 7, 1967, the date of a Warranty Deed from Mitchell E. Burnes to Kathleen E. Brown, which deed was recorded in the Cumberland County Registry of Deeds in Book 3017, Page 15, through July 12, 2000 at 8:00 a.m. and we found no encumbrances affecting the subject premises during the period of our update.

For your information, we found nothing in our research which would indicate that Ms. Brown owns anything less than a full interest in the subject premises. Furthermore, Ms. Brown did not inherit the Stratton Place (formerly known as Park Place) property from her parents. Rather, she acquired the property from Mitchell E. Burns in 1967, having first entered into a Bond for Deed Agreement with Mr. Burns on April 1, 1958.

Of course, if you have any questions or need any further research done in this matter, please give me a call at your convenience.

Very truly yours,

ANDROSCOGGIN TITLE COMPANY



William K. Skelton, Esq.

WKS/mcs  
N:\WPDOCS\MICHELLE\MISC\BROWN.LTR

10 STRATTON Project #1

Floor Plan

Top View

