

*[Handwritten signatures and scribbles]*

**RECEIVED**  
 JAN 16 2017  
 By Evans

**CITY OF PORTLAND**  
**FIRE PREVENTION BUREAU**  
 380 Congress Street, Portland, Maine 04101  
 fireprevention@portlandmaine.gov  
 (207) 874-8400

**NOTICE OF VIOLATION AND ORDER TO CORRECT**

December 20, 2016

<b>Responsible Party 1:</b> Price Apartments LLC 177 Buck & Doe Tr Augusta, ME 04330		<b>Responsible Party 2:</b> Mainly Property Management 188 Dartmouth St Portland, ME 04103
<b>Location</b> 32 STATE ST	<b>CBL</b> 044 C008001	<b>Inspection Date</b> 8/22/2016
<b>Inspector</b> David Petruccelli	<b>Inspection Type</b> FP Re-Inspection	<b>Status</b> Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must complete the proposed date of completion column by proposing a reasonable timeframe to remedy each violation. This form must be received by the Fire Prevention Bureau no later than 1/15/2017. The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

**YOUR FAILURE TO SUBMIT A PLAN OF ACTION BY THE DATE PROVIDED, OR TO CORRECT ANY VIOLATION WITHIN THE APPLICABLE TIME FRAME, MAY RESULT IN LEGAL ACTION AGAINST YOU, THE IMPOSITION OF CIVIL PENALTIES, AND THE PURSUIT OF OTHER LEGAL REMEDIES.**

Violation	Proposed Date of Completion
<i>5/4" thick plywood</i> <b>NFPA 101-7.2.4.3.1 FIRE BARRIER REQUIRES MAINTENANCE;</b> Fire barriers separating buildings or areas between which there are horizontal exits shall have a minimum 2-hour fire resistance rating, unless otherwise provided in 7.2.4.4.1, and shall provide a separation that is continuous to the finished grounded level. <i>Next week</i> Unprotected interior "window" in both 30 & 32 required to be fire rated into exit stair.	<u>2 / 1 / 17</u>
<i>There are floors on each level and ceiling</i> <b>NFPA 101- 31.3.1.1.1 VERTICAL OPENINGS NOT FIRE RATED;</b> Vertical openings shall be enclosed or protected in accordance with Section 8.6. Vertical shaft not rated from basement to cockloft, old dumbwaiter shaft being used for mechanical and electrical chase	<u>3 / 10 / 17</u>
<b>NFPA 101-31.3.4.1.1 FIRE ALARM SYSTEM REQUIRED;</b> Apartment buildings four or more stories in height or with more than 11 dwelling units, other than those meeting the requirements of 31.3.4.1.2, shall be provided with a fire alarm system in accordance with Section 9.6, except as modified by 31.3.4.2 through 31.3.4.6. 4 stories & more	<u>5 / 3 / 17</u>
<b>NFPA 101- 7.2.1.8.1 FIRE DOORS MUST BE SELF- OR AUTO-CLOSING;</b> A door leaf normally required to be kept closed shall not be secured in the open position at any time and shall be self-closing or automatic-closing in accordance with 7.2.1.8.2, unless otherwise permitted by 7.2.1.8.3. Adjust hinges in all apartments, must close fully and latch <i>Done</i>	<u>2 / 1 / 17</u>
<b>PORTLAND CHAPTER 10 CODE SECTION 12 KNOX BOX REQUIRED;</b> Knox boxes are required for all buildings with fire alarm or suppression systems. Properties with alarm systems <i>Ordered</i>	<u>2 / 1 / 17</u>

*5/4" thick plywood*  
*There are floors on each level and ceiling*  
*18 Additions*

*Installed 09/22/16*  
*5700*

*3,071* | *96,000*

*19*

Violation	Proposed Date of Completion
<b>NFPA 720- 5.5.6.1 CO ALARMS REQUIRED;</b> The performance, location, and mounting of notification appliances used to initiate or direct action, evacuation or relocation of the occupants, or for providing information to occupants or staff, shall comply with the requirements of Chapter 6. On every level <span style="float: right;">Done 1/15/17</span>	1 / 15 / 17
<b>NFPA 101- 31.3.3.2 INTERIOR FINISH;</b> Interior wall and ceiling finish materials complying with 10.2 shall be permitted as follows: (1) Exit enclosures- Class A or B (2) Lobbies and corridors- Class A or B (3) Other Spaces- Class A, B, or C. Paneling in rear stair, needs fire retardant paint or to be removed and repair plaster.	2 / 1 / 17
<b>NFPA 70- ARTICLE 110.12 B EXPOSED WIRING CONNECTIONS;</b> Internal parts of electrical equipment, including busbars, wiring terminals, insulators, and other surfaces, shall not be damaged or contaminated by foreign materials such as paint, plaster, cleaners, abrasives, or corrosive residues. There shall be no damaged parts that may adversely affect safe operation or mechanical strength of the equipment such as parts that are broken; bent; cut; or deteriorated by corrosion, chemical reaction, or overheating. Multiple locations in hall ways <span style="float: right;">Done 1/15/16</span>	1 / 15 / 17
<b>NFPA 70 MISSING BOX COVERS;</b> Refer to NFPA 70, National Electrical Code, on standards for missing box covers. Several location in basement <span style="float: right;">Done 1/16/16</span>	1 / 15 / 17
<b>NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED;</b> Refer to NFPA 101- Table 8.3.4.2 that states fire door assemblies for vertical shafts (including stairways, exits, and refuse chutes) are rated and required for 1 hour. basement stairs both sides	2 / 1 / 15

**VIOLATOR CERTIFICATION**

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.

1/14/17  
 \_\_\_\_\_  
 Date

Mairely Property Management  
 \_\_\_\_\_  
 Responsible Party

\_\_\_\_\_  
 Date

\_\_\_\_\_  
 Responsible Party

**SEEN AND AGREED**

17 Jan. 2017  
 \_\_\_\_\_  
 Date

Cpt. Petrucci  
 \_\_\_\_\_  
 Fire Prevention Bureau