

7/27/16

City of Portland Fire Dept

re: William E. Honan, 164 Danforth St.

This is to state that I am a licensed electric contractor in the State of Maine and on this date I installed a grounded outlet behind the washer machine in the basement at 164 Danforth so the cord from the washer can be plugged into it without use of an extension cord. I further state that there are NO extension cords being used in the basement of this property, the owner has removed the utility light over the work bench that apparently also had an extension cord.



Honan's electric

767-2471



Ryan Piper

HANNAN ELECTRIC

**CITY OF PORTLAND
PORTLAND FIRE DEPARTMENT**

380 Congress Street
Portland, Maine 04101

Inspection Violations

Owner/Manager Honan William E		Inspector Steven Hall	Inspection Date 7/7/2016
Location 164 Danforth	CBL 044 D029001	Status Failed	Inspection Type Fire Company-FP Routine Inspec

Code	Int/Ext	Floor	Unit No.	Area	Compliance Date
1) 73.15					
Violation:	NFPA 101- 31.3.1.1.1 VERTICAL OPENINGS NOT FIRE RATED; VERTICAL OPENINGS SHALL BE ENCLOSED OR PROTECTED IN ACCORDANCE WITH SECTION 8.6.				
Notes:	PANELING IN STAIWELLS				
2) 89.05					
Violation:	NFPA 1 EXCESSIVE/DISORDERLY STORAGE; REFERENCE NFPA 1 FOR EXCESSIVE FUEL-LOAD.				
Notes:	STORAGE IN STAIRWELLS				
3) 89.15					
Violation:	NFPA 30- TABLE 9.6.2.1 FLAMMABLE/COMBUSTIBLE LIQUIDS STORAGE EXCEED LIMIT; SEE NFPA 30 TABLE 9.6.2.1 FOR SPECIAL OCCUPANCY LIMITS FOR FLAMMABLE AND COMBUSTIBLE LIQUID STORAGE.				
Notes:	5 GALLON CAN IN THE BASEMENT				
4) 91.20					
Violation:	NFPA 70- 590.6 EXTENSION CORDS; Ground-fault protection for personnel for all temporary wiring installations shall be provided to comply with 590.6(A) and (B). This section shall apply only to temporary wiring installations used to supply temporary power to equipment used by personnel during construction, remodeling, maintenance, repair, or demolition of buildings, structures, equipment, or similar activities.				
Notes:	USE OF EXTENSION CORDS IN THE BASEMENT				
5) 3.011					
Violation:	NFPA 101- 31.3.2.1.1 BOILER PROTECTION REQUIRED; THE AREAS DESCRIBED IN TABLE 31.3.2.1.1 SHALL BE PROTECTED AS INDICATED: BOILER AND FUEL-FIRED HEATER ROOMS SERVING MORE THAN A SINGLE DWELLING UNIT (MINIMUM SEPARATION/PROTECTION IS 1 HOUR OR SPRINKLERS)				
Notes:	NEED BOILER PROTECTION				
6) 80.37					
Violation:	NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED; REFER TO NFPA 101- TABLE 8.3.4.2 THAT STATES FIRE DOOR ASSEMBLIES FOR VERTICAL SHAFTS (INCLUDING STAIRWAYS, EXITS, AND REFUSE CHUTES) ARE RATED AND REQUIRED FOR 1 HOUR.				
Notes:	NEED FIRE DOORS				
Comments:					

DEDICATED
CIRCUIT.

