

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

TERENZONI ROBERT S & DENISE M TERENZONI JTS

Located at

16 TATE ST

PERMIT ID: 2015-00214

ISSUE DATE: 03/30/2015

CBL: 044 E011001

has permission to **Alterations including extending shed dormer, revised framing to change stairway location and all interior finishes of the project (in addition to existing permit #2014-02338)**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise clsoed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

N/A

/s/ Laurie Leader

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

two family

Building Inspections

Use Group:

Two family

ENTIRE

MUBEC/IRC 2009

Type:

Fire Department

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

**Check the Status or Schedule an Inspection On-Line at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

Foundation/Backfill

Close-in Plumbing/Framing

Above Ceiling Inspection

Electrical Close-in

Final - Fire

Certificate of Occupancy/Final

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2015-00214	Date Applied For: 01/28/2015	CBL: 044 E011001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Two Family	Proposed Project Description: Alterations including extending shed dormer, revised framing to change stairway location and all interior finishes of the project (in addition to existing permit #2014-02338)			
<p>Dept: Zoning Status: Approved w/Conditions Reviewer: Ann Machado Approval Date: 03/10/2015</p> <p>Note: *using section 14-436(b) for dormers. Ist floor footprint is 1045 sf - adding 342 sf with the two dormers - Ok to Issue: <input checked="" type="checkbox"/> 342/1045 = 32.7% increase in floor area. Allowed an 80% increase - OK</p> <p>Conditions:</p> <ol style="list-style-type: none"> 1) This property shall remain a two family dwelling. Any change of use shall require a separate permit application for review and approval. 2) This permit is being approved on the basis of plans submitted. Any deviations shall require a separate approval before starting that work. 				
<p>Dept: Building Inspecti Status: Approved w/Conditions Reviewer: Laurie Leader Approval Date: 03/30/2015</p> <p>Note: Ok to Issue: <input checked="" type="checkbox"/></p> <p>Conditions:</p> <ol style="list-style-type: none"> 1) Tempered safety glazing is required at all hazardous locations per IRC 2009 Sec. R308.4 and IBC 2009 Sec. 2406.4 2) Where supported by attachment to an exterior wall, decks shall be positively anchored to the primary structure and designed for both vertical and lateral loads as applicable. Such attachment shall not be accomplished by the use of toenails or nails subject to withdrawal. See IRC 2009 Sec. 502.2.2 and IBC Sec. 1604.8.3 for details. <p>Deck lateral load connection shall be allowed with hold-down tension devices installed in not less than two locations per deck, with each device having an allowable stress design capacity of not less than 1500 pounds.</p> <p>Where positive connection to the primary building structure cannot be verified during inspection, decks shall be self-supporting.</p> <ol style="list-style-type: none"> 3) All floors and walls that separate dwelling units or dwelling units and common areas are required to meet a 1 hour fire rated assembly and sound transmission rating of 45 STC. 4) The design load specification sheets for any engineered beam(s)/trusses must be submitted to this office. 5) Hardwired photoelectric interconnected battery backup smoke detectors shall be installed in all bedrooms, protecting the bedrooms, and on every level. <p>The same is required for existing buildings, where permanent wiring is feasible; or at the very least battery operated smoke detectors are required. Verification of this will be upon inspection.</p> <ol style="list-style-type: none"> 6) Separate permits are required for any electrical, plumbing, sprinkler, fire alarm, HVAC systems, heating appliances, including pellet/wood stoves, commercial hood exhaust systems, fire suppression and fuel tanks. Separate plans may need to be submitted for approval as a part of this process. 7) Egress size windows are required (1) in each bedroom per IRC Sec. R310 or per the State Fire Marshall policies for existing buildings. 8) The continuity of the fire resistance rated wall or floor/ceiling assembly shall be installed and maintained as described in IBC Ch. 7 and all penetrations shall be treated with approved materials and methods. 9) A copy of the enclosed chimney or fireplace disclosure must be submitted to this office upon completion of the permitted work or for the Certificate of Occupancy. 10) Carbon Monoxide (CO) alarms shall be installed in each area within or giving access to bedrooms. That detection must be powered by the electrical service (plug-in or hardwired) in the building and battery. 				

11 This permit is approved based upon information provided by the applicant or design professional. Any deviation from the final approved plans requires separate review and approval prior to work.