Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 05/16/16

FOUNDATION PLAN

1/4"=1'-0"

TOP OF CONCRETE WALL ELEV. NOTED (XX'-X").

TOP OF CONCRETE WALL AT SLAB SHELF AND DOOR BONDOUTS = 97'-3 1/2" UNLESS NOTED.

BOTTOM OF FOOTING ELEV. NOTED B/FTG = XX'-X". FOOTINGS STEPS MAY BE RELOCATED AS DETERMINED BY CONTRACTOR AS LONG AS A MINIMUM OF 4'-0" FROM BOTTOM OF FOOTING TO FINISHED GRADE IS MAINTAINED.

TOP OF SLAB ELEV. VARIES - SEE PLAN.

DIMENSIONS NOTED * MUST BE VERIFIED WITH LIFT REQUIREMENTS.

SLAB IS 4" THICK FIBER-REINFORCED CONCRETE OVERLAYING A VAPOR BARRIER ON RIGID INSULATION OVER AN 8" LAYER OF 3/4" GRAVEL.

. . . . . INDICATES SAW-CUT CONTROL JOINT.

COORDINATE DOOR BONDOUT SIZES AND LOCATIONS WITH ARCHITECTURAL DRAWINGS AND DOOR SUPPLIER REQUIREMENTS.

SEE S0.01 FOR FOOTING FOOTING AND COLUMN SCHEDULES.

Prepared For:
TATE STREET
PARTNERSHIP, LLC
17 Chestnut Street
Portland, Maine 04101

Consulting Engineer:
STRUCTURAL DESIGN CONSULTING
2696 Lake Shore Road
Unit 1-130
Gilford, NH
03249
Tel 603.293.8038

Architect:
ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
WEST PORT LOFTS
CONDOMINIUM
22-28 Tate Street
Portland, Maine

Revisions:
Issued for Foundation Permit 03/21/16

Scale: 1/4"=1'-0"

Date: 21 MAR 2016

FOUNDATION PLAN

S1.01