

SimplexGrinnell Material List (THIS IS NOT A PRICE QUOTATION)

TO:
 B H Milliken
 175 Anderson St
 PORTLAND, ME 04101-2550
 Attn: Wes Milliken
 (207) 879-1877 EXT() Fax:

Project: Elm Terrace II - Portland
 Customer Reference: Fire Alarm & Door Intercom
 SimplexGrinnell Reference: 147420360
 Date: 02/29/2012
 Page 1 of 3

QUANTITY	MODEL NUMBER	DESCRIPTION
4010ES Fire Alarm System		
Fire Alarm Devices		
4010 FACP Batteries		
1	4010-9401	4010ES FACP 120V RED
1	4010-9912	SERIAL DACT
2	2081-9275	BATTERY 18AH
AES Radio Master Box		
1	7788-F	8ZONES W/2.5DB RED
1	BD7-12	12V 7AH SEALED LEAD ACID
1	1640	UL TRNSFR FOR 7750-F SUBSCRIBE
5	4090-9002	RELAY IAM
1	SG Switch	DISCONNECT SWITCH
1	ADI GSW TSW-01S	TAMPER SWITCH
Knox Box		
1	3270	KNOX BOX 3270
Pull Stations		
7	4099-9003	MANUAL STATION - DOUBLE ACTION
Duct Smoke Sensors		
4	4098-9756	DUCT SENSOR HOUSING-4-WIRE
4	2098-9806	REMOTE TEST STATION
4	2098-9798	SAMPLING TUBE 73"
Smoke Sensors		
74	4098-9714	PHOTO SENSOR
70	4098-9792	SENSOR BASE
4	4098-9797	SSD SENSOR BASE WITH CO MODULE
Heat Sensors		
4	4098-9733	HEAT SENSOR
3	4098-9792	SENSOR BASE
1	4098-9797	SSD SENSOR BASE WITH CO MODULE
120VAC Smokes and CO Detectors		
83	7109CS-C	PE SMK 120V/9V W/STROBE CEILIN
38	5120BN	BRK 120VAC CO DETECTOR
Sprinkler Monitoring		
12	4090-9001	SUPERVISED IAM
12	4090-9810	BRACKET, IAM
12	4090-9806	COVER-ADDRESS MODULE FLUSH
Elevator Recall		
4	4090-9002	RELAY IAM
4	4090-9801	COVER-ADDRESS MODULE FLUSH
Notification Devices		

SimplexGrinnell Material List (THIS IS NOT A PRICE QUOTATION)

QUANTITY	MODEL NUMBER	DESCRIPTION
10	4906-9101	STROBE MC RED
38	4906-9103	STROBE MC WHITE
47	4906-9127	HORN/STROBE MC RED
83	4906-9129	HORN/STROBE MC WHITE
	NAC Booster Panels	
2	4009-9201	NAC EXTENDER 120VAC, IDNET
4	2081-9272	BATTERY 6.2 AH
	Fire Alarm Permit Ethernet Drop	
1	ETHEDROP	ETHERNET DROP REQUIRED AT FACP
	Door Intercom System Door Intercom Materials	
1	AM492P	PNL VNDL SPEAKER 0 BTN
1	CM492/044	MASTER INTERCOM
1	CM490/048	APT PANEL 48 BTN ADD-ON
2	AM190D	PNL APT DIR 60 NAME OF 190 FRA
1	OH192	HOUSING
1	OF192	FRAME
1	OH193	HOUSING 3G
1	OF193	FRAME 3G
1	PK543A	AMPLIFIER
1	PK502B	DUAL ENTRANCE CONTROL
1	SS102A	TRANSFORMER
2	PO001	ELEC DOOR OPENER 16VAC
38	IR204E	REMOTE STATION
3	LI404B	STROBE UNIT

Comments

Scope of Work:

SimplexGrinnell is pleased to provide this proposal for a Fire Alarm System & Door Intercom System for the proposed Elm Terrace project, Portland, ME. Proposal is per plans E2.0, E3.0 through E3.8 dated 9/8/11 and Specification 26 00 00 Section 2.13 Fire Alarm System and 2.15 Apartment Intercom/Security Systems. **Counts provided are those as provided by BH Milliken on 12/12/11.**

Per your request unit pricing as it relates to the TekTone Strobe Only is \$90.00 each.

Proposal is based on counts and material requested.

This quotation is based on the acceptance of delivery of all equipment within one year.

This quotation does not include back boxes or adapter plates for surface mount devices unless so listed.

SimplexGrinnell Material List (THIS IS NOT A PRICE QUOTATION)

Comments (continued)

Wire /Cable: Upon written request, Simplex will provide written instruction regarding the appropriate wire/cable for installation of the equipment/system(s) identified in this quotation. Simplex shall not be responsible for problems or damages resulting from the use of any wire/cable other than that which has been identified in writing by Simplex for a specific application.

All panel & peripheral installation is the responsibility of the Electrical Contractor unless otherwise agreed upon in writing with SimplexGrinnell. SimplexGrinnell is responsible for panel terminations, system programming, test (with EC assistance) and overall system commission.

Proposal includes 1 hour customer training at time of system commission for the end user for each system proposed.

Technical Labor & Testing is based on being performed between 8AM and 5PM, Monday-Friday excluding holidays.