

**GAWRON TURGEON ARCHITECTS**  
 29 Mack Point Road  
 Scarborough, ME 04074  
 www.gawronturgen.com  
 Tel: 207 883 5707  
 Fax: 207 883 0161

**SEVENTY-FIVE STATE STREET**  
 HARBORSIDE, SOUTH FOURTH FLOOR RENOVATIONS  
 PORTLAND, MAINE


REVISIONS	
#	DATE

DATE:	3/30/07
PROJECT #:	010206
DRAWN BY:	KW
CHECKED BY:	
DRAWING SCALE:	3/16"

SHEET TITLE:  
 FOURTH FLOOR DEMO  
 FLOOR PLAN

**D101**

© COPYRIGHT 1989-2001  
 GAWRON TURGEON ARCHITECTS  
 29 MACK POINT ROAD  
 SCARBOROUGH, ME 04074  
 TEL: 207 883 5707  
 FAX: 207 883 0161  
 WWW.GAWRONTURGEN.COM



**DEMO KEY LEGEND**

- 01 REMOVE ALL DRYWALL AND FURRING STRIPS DOWN TO THE EXISTING MASONRY WALL
- 02 REMOVE AND DISPOSE OF ALL EXISTING KITCHEN AND BATHROOM FIXTURES AND APPLIANCES
- 03 REMOVE ANY EXISTING FINISHED FLOOR INCLUDING CARPET AND SHEET VINYL
- 04 ALL DOTTED PARTITIONS, FIXTURES, AND DOORS TO BE REMOVED EXCEPT AS NOTED.
- 05 EXISTING SHEETROCK/PLASTER TO REMAIN
- 06 EXISTING DOOR TO REMAIN
- 07 EXISTING STAIRS TO REMAIN. PROTECT DURING DEMOLITION.
- 08 EXISTING WINDOWS TO REMAIN UNTIL FULL CONSTRUCTION OCCURS
- 09 BEAM ABOVE TO REMAIN
- 10 EXISTING STRUCTURAL CONCRETE FILLED CMU TO REMAIN

**DEMO NOTES:**

1. NO WORK TO BE DONE ON EXTERIOR AT THIS TIME.
2. ALL LIGHTING, OUTLETS, WIRING, SMOKE DETECTORS, AND PANELS TO BE REMOVED. ELECTRIC AND LIFESAFETY SYSTEMS MUST BE MAINTAINED FOR FLOORS BELOW DURING AND AFTER DEMOLITION.
3. ENTIRE SPRINKLER SYSTEM TO BE REMOVED. EXISTING SPRINKLER SYSTEM FOR THE REMAINING BUILDING MUST BE MAINTAINED FOR FLOORS BELOW DURING AND AFTER DEMOLITION.
4. ENTIRE EXISTING HEATING AND PLUMBING SYSTEM TO BE REMOVED. HEATING AND PLUMBING FOR FLOORS BELOW MUST BE MAINTAINED DURING AND AFTER DEMOLITION.
5. ALL EXISTING DOORS, EXCEPT EXISTING 2 HR RATED STAIR ENCLOSURE DOORS, TO BE REMOVED.
6. REMOVE ALL DRYWALL OR GYP ON ALL CEILINGS, EXCEPT STAIR ENCLOSURES, ON ENTIRE 4TH FLOOR OF THIS BUILDING.

**A1 FIRST FLOOR-DEMO PLAN**

**DEMOLITION DRAWINGS**