



NOTE: ALL PIPING AND DUCTWORK PENETRATIONS THROUGH FIRE RATED WALLS AND FLOORS SHALL BE EQUIPPED WITH UL APPROVED FIRE COLLARS, INTUMESCENT FIRE CAULKING AND FIRE DAMPERS AS REQUIRED BY CURRENT BUILDING CODES AND TO THE SATISFACTION OF THE LOCAL CODE ENFORCEMENT AUTHORITY

INSTALL 1-1/2 HOUR UL CLASSIFIED FIRE DAMPER AT 4TH FLOOR LEVEL ON ALL BATHROOM EXHAUST SYSTEMS; PROVIDE ACCESS DOOR FOR EACH FIRE DAMPER (TYP. OF 7)

SIDE WALL DRYER EXHAUST: TERMINATE EXHAUST DUCT WITH WALL CAP/BDD COMBINATION TO MATCH EXISTING ARCHITECTURE (TYP. OF 7)

EXISTING BATHROOM EXHAUST DUCT IN WALL CHASE TO BE TIED INTO AND REUSED (TYP. OF 7)

MOUNT ALL THERMOSTATS TO MEET ADA REQUIREMENTS (TYP. OF 7)

4TH FLOOR HVAC PLAN

SCALE: 1/4" = 1'-0"

**75 STATE STREET
PORTLAND, ME
HARBORSIDE SOUTH
4TH FLOOR HVAC PLAN**

PROJECT NUMBER:	42096
ISSUED:	9-10-07
DRAWN BY:	MGR
CHECKED BY:	DWM / CB
FILENAME:	.DWG