


Mid State Sheetmetal



Estimate

Estimate No: 106
Date: May 10, 2015

119 Packard Rd
Monmouth Me, 04259
Cel Phone: 1-207-441-7350

1-207-933-5603
1-207-441-7350
1-207-933-6857
Dick.metalman@gmail.com

For: The Danforth
Danforth St
Portland Maine
Tele: 542-4999

Description

Quantity

Rate

Amount

This is in regards to the installation of the exhaust hood system at the Danforth.
The exhaust duct will not be in a chase. The duct will be exposed in the kitchen area close to the ceiling. But as outlined in the current NFPA 96 catalog all duct will be made of 16 ga steel and joints will be of welded construction. Any duct that is within 18 inches of combustibles will be wrapped with industry standard fire master grease duct wrap. To meet the code for clearance reduction in NFPA 96 pg 96-33
Section a.4.2

1

\$0.00

\$0.00

* Indicates non-taxable item

Subtotal

\$0.00

TAX (5.50%)

\$0.00

Total

\$0.00