Submittal Data: 9RLFW ASU9RLF& AOU9RLFW

FUjitsu

Job Name:		Location:							
Purchaser:									
Engineer:									
Submitted To:		For:		Reference	e 🗆	Approval		Construction	
Submitted By:									
Unit Designation: Schedule No.		Model No	o.:						
Capacities:				Ουτι			SION	IS	
Cooling	9,000 BTU/h								
Outdoor Design Temp. Fo DB/WB	95/75								
Heating	12,000 BTU/h								
Outdoor Design Temperature Fo DB/WB	47/43		<		31-1/16		1	8	
HSPF	11.0	1		1			5		
SEER	23.0	16							
EER Cooling/Heating	13.8/13.47	11-1/16							
Voltage/Frequency/Phase	208-230/60/1	Ţ						K I CE	
Indoor Unit:									
Noise Level Cooling <i>db</i> (A) - H/ M/ L/ Q	37/ 33/ 29/ 25								
Noise Level Heating <i>db</i> (A) - H/ M/ L/ Q	37/ 33/ 29/ 25								
Weight	18 lbs.								
Outdoor Unit:				2	6		-	11-7/16	
Noise Level Cooling/Heating	48/48	1 2	-				<u>ج</u>		
Recommended Fuse Size	15A								
Min. Ampacity	4.2A								
Running Current Cooling	6.0A	21-1/4							
Running Current Heating	7.5A	51							
Weight	71 lbs.								
Refrigerant Piping:							I		
Max Ht. Difference	49 ft.	<u>د ا</u>	2		11	<u> </u>			
Max Total or Combined Length	66 ft.								
Discharge Vapor Line (O.D.)	1/4 in.								
Suction (O.D.)	3/8 in.								
Seven year compressor warranty	 ENERGY STAR® Qualified 				Optional Wired Remote Control				
• Five year parts warranty	• Built in Low Ambient to 14°F				Dry mode				
Digital wireless remote control	Auto Restart/ Reset				Refrigerant R410A				
• Auto Louver: Up/Down	• 24 hour timer					iet Mode			
Notes:									