

GENERAL NOTES:

1. FIRE ALARM SYSTEM WIRING SHALL COMPLY WITH THE NATIONAL ELECTRICAL CODE, APPLICABLE STATE AND LOCAL CODES, AND SHALL BE COORDINATED WITH THE LOCAL AUTHORITY HAVING JURISDICTION.

2. CAUTION: DO NOT CONNECT ANY POWER TO THE CONTROL PANEL (BATTERIES OR 120V AC) UNTIL ALL OTHER FIELD WIRING IS TESTED AND CONNECTED.

3. DO NOT INSTALL FIRE ALARM CONTROL PANEL OR SMOKE DETECTORS IN AN UNHEATED AREA.

4. DO NOT INSTALL ANY AC CURRENT-CARRYING CONDUCTORS CLOSE TO OR IN THE SAME RACEWAY WITH FIRE ALARM SYSTEM CONDUCTORS.

5. SOLID LINES REPRESENT CONNECTIONS TO BE MADE BY THE SYSTEM INSTALLER.

6. SEE MODEL _____ INSTALLATION MANUAL FOR ADDITIONAL WIRING INSTRUCTIONS.

7. ALL RELAYS ARE SHOWN IN NORMAL SUPERVISORY CONDITION. ALL RELAYS ARE FORM "C" TYPE.

INSTALLATION NOTES

- SMOKE DETECTORS SHALL NOT BE MOUNTED ANY CLOSER THAN 3' FROM ANY AIR DUCT OPENINGS
- 2. ELEVATOR LOBBY SMOKE DETECTORS SHALL BE MOUNTED WITHIN 10' OF THE ELEVATOR DOOR
- MANUAL PULL STATIONS SHALL BE MOUNTED PER ADA REQUIREMENTS: 48" AFF OR 42" AFF TO COMPLY WITH SIDE/FRONT REACH REQUIREMENTS
- WALL MOUNTED HORN/STROBES & STROBES SHALL BE MOUNTED 6" FROM CEILING, OR 96" TO 80" AFF TO THE CENTER OF STROBE
- HORN/STROBES & STROBES SHALL BE MOUNTED 15' FROM THE CORNER OF THE WALL. IF THIS IS NOT POSSIBLE, DEVICE SHALL BE CENTERED ON THAT WALL.
- 6. CEILING MOUNTED HALLWAY DEVICES SHALL BE LOCATED IN A SYMMETRICAL MANNER DOWN CENTER OF HALLWAY WHEN POSSIBLE

SMOKE DETECTOR

S ELEVATOR RECALL SMOKE DETECTOR

s 120 VOLT SMOKE DETECTOR (NOT CONNECTED TO FACP)

HI-DECIBEL HORN/STROBE (NOTE CD RATING)

SINGLE GANG HORN

PULL STATION

REMOTE LED 120 VAC (NOT CONNECTED TO FACP)

4" BELL (NOT CONNECTED TO FACP)

DA horn strobe

CONSULTANT PROTECTION PROFESSIONAL

SAINT DOMINIC'S FAMILY HOUSING

SECOND & THIRD FLOOR
DEVICE LAYOUT & WIRING

Ω

REVISIONS

DATE: 06/12/03


SCALE: NTS

DRAWN: CTS

APPROVED: SFA

F-2

SECOND FLOOR



F-3