

KEY NOTES (ALL FLOORS)

- ◆ One-hour fire rated wall: (1) Layer 5/8" F.S. Gyp. on each side of 3 1/2" metal stud @ 12" o.c., (provide resilient channel one side with sound attenuating blankets & wall separation walls only).
- ◆ Acoustical wall: 3 1/2" metal stud wall with resilient channel on one side with sound attenuating blankets and 3/8" GWS both sides.
- ◆ 3 1/2" metal stud with 5/8" GWS both sides.
- ◆ Existing exterior wall with 2-furring, 2" rigid insulation and 5/8" GWS.
- ◆ Masonry wall construction.
- ◆ Two hour fire rated wall: 3 1/2" metal stud @ 12" o.c. with (1) Layer 5/8" F.S. Gyp. on each side. (Provide resilient channel on one side with sound attenuating blankets & wall separation walls only).

GENERAL NOTES (ALL FLOORS)

1. Information shown pertaining to existing conditions is based upon visual inspection and existing construction documents used by the Architect. Any discrepancies discovered by others shall be brought to the attention of the Architect.
2. General Contractor shall check and verify all existing conditions and dimensions at the site.
3. ~~_____~~
4. All rated walls shall extend up to the underside of floor or roof deck above, unless otherwise noted.
5. Verify sizes and locations of all louvers, openings and concrete pads required by mechanical and electrical equipment.
6. All openings around pipes, ductwork, etc. that penetrate walls or floors shall be sealed. All work and sealant materials shall be approved by the Architect.
7. Adequate emergency exits must be maintained throughout construction.
8. Equipment and furnishings suppliers shall field verify all dimensions for new items before fabrication and installation.
9. General Contractor to install wood or metal blocking as required for installation of casework, millwork and accessory items.
10. General Contractor shall coordinate work with all other trades.
11. All metal studs shall be 3 1/2" unless otherwise noted or detailed.
12. Allow shafts to be closely as possible floor to floor; coordinate with mechanical contractor.
13. All shafts to be 2 hour fire rated with 2 layers of 5/8" GWS at all surface continuous to roof deck with fire rated shaft at all joints.
14. Prior to infill of exterior masonry, contractor shall submit samples of brick and mortar to Architect for approval. A sample panel within an existing wall may be necessary for historic approval.
15. Cleanup shall be required at the service entrance to the building, at all apartment unit entry doors, public collect, all trash rooms. All electrical rooms, all mechanical rooms and the managers office.
16. Signage shall comply with the Americans with Disabilities Act for character appearance, character height, raised and Braille requirements, finish and contrast, and mounting location and height. Samples will be required for approval by the Architect.
17. Demolition of the retail space will entail the following:
 - A. Remove all non-loadbearing interior partition walls and structurally unsound trimwork.
 - B. Remove all partition or other applied materials from the walls to remain.
 - C. Remove flooring as necessary to get down to a hard surface to accept new flooring at a later date.
 - D. Remove all suspended ceiling systems and associated equipment.
 - E. Prime all walls with one coat of primer.
 - F. Provide all of the architectural, mechanical, electrical and plumbing modifications as shown on drawings.
18. ALL DIMENSIONS SHALL TO FACE UNLESS OTHERWISE NOTED.
19. ~~_____~~

CH2M HILL
 317 Liberty Street
 Portland, ME 04103
 617-725-1332
 FAX 617-725-8110

317 Liberty Street
 Portland, ME 04103
 617-725-1332
 FAX 617-725-8110

PORTLAND
 ME 04101
 317
 LIBERTY
 STREET
 PORTLAND
 ME 04103

PORTLAND ME 04101


317
 LIBERTY
 STREET
 PORTLAND
 ME 04103

DATE: 04/29/99

APR 29 1999
 10:54 AM
 DOWN BY: EJS
 SHEET: A-2

APR 29 1999
 10:54 AM
 DOWN BY: EJS
 SHEET: A-2

APR 29 1999
 10:54 AM
 DOWN BY: EJS
 SHEET: A-2



FIRST FLOOR PLAN (PART A)
11'-1'-0"

