Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 02/25/15

Dec 2014

cond Floor

		Size	Frame Data		Door Data		HW Set	Notes
201	Waiting to Reception	3070	HM 16 ga	LH	Wood: full glass	RHR	Lock	Sidelight frame
202	Elevator lobby to waiting	3070	HM 16 ga	LH	Wood: full glass	RHR	Lock	Sidelight frame
203	Elevator lobby to Storage	Existing door and frame to remain						
204	Elevator to bath	Existing door and frame to remain						
205	Rental space to bath	Existing door and frame to remain						
206	Elevator lobby to Rental	3070	HM 16 ga	LH	Wood: Full glass	LH	Lock	
207	Elevator lobby to Lab	3070	HM 16 ga	RH	Wood: narrow light	RH	Lock	
208	Corridor 1 to Closet	6070	HM 16 ga	Pair	Wood: flush	N/A	Ball catch	
209	Corridor 1 to Corridor 2	3070	HM 16 ga	RH	Wood: half light	RH	passage	
210	Corridor 1 to Bath	3070	HM 16 ga	LH	Wood: flush	RH	privacy	
211	Corridor 1 to Stair	Existing door and frame to remain						
212	Corridor 2 to Office	3070	HM 16 ga	RH	Wood: half light	RH	Lock	
213	Corridor 2 to Bath	Existing door and frame to remain						
214	Break Room to Lockers	3070	HM 16 ga	LH	Wood: flush	LH	passage	
215	Reception to Break room	3070	HM 16 ga	LH	Wood: half light	LH	passage	
216	Lab to Stair	Existing door and frame to remain						
217	Stair to Rental Space	3070	HM 16 ga	RH ULB	HM: narrow light	RH	Lock	
218	Lab to Lab Bath	3070	HM 16 ga	RH	Wood: flush	RH	privacy	
219	Lab to Lab Office	3070	HM 16 ga	LH	Wood: half light	LH	Lock	
220	Lab Corridor to Fabrication	3070	HM 16 ga	LH	Wood: half light	LH	Lock	
221	Lab Corridor to Corridor 1	3070	HM 16 ga	LH	Wood: TBD	LH	passage	Door pending salvage
222	Corridor 1 to Work Area	3070	HM 16 ga	RH	Wood: TBD	RH	passage	Door pending salvage
223	Corridor 1 to Tech	3070	HM 16 ga	RH	Wood: TBD	RH	Lock	Door pending salvage
224	Corridor 1 to Storage	3070	HM 16 ga	LH	Wood: flush	RHR	Lock	
225	Closet	3070	HM 16 ga	LH	Wood: flush	RHR	Passage	
226	Corridor 3 to Bath	3070	HM 16 ga	LH	Wood: flush	LH	privacy	
227	Corridor 3 to Office	3070	HM 16 ga	RH	wood: TBD	LHR	passage	Door pending salvage