
SMOKE , HEAT AND CO DETECTORS ARE WIRELESS. ALL OTHER DETECTORS ARE HARD WIRED TO THE FACP


15cd

SINGLE IMPUT

MODULE

SIM





STROBE

PROTECTION

PROFESSIONALS

GENERAL NOTES

A.)FIRE ALARM SYSTEM WIRING SHALL COMPLY WITH THE NATIONAL ELECTRIC CODE, APPLICABLE STATE AND LOCAL CODES AND SHAL BE COORDINATED WITH THE LOCAL AUTHORITY HAVING JURISDICTION.

- B.) CAUTION; DO NOT CONNECT ANY POWER TO THE CONTROL PANEL(BATTERIES OR 120VAC) UNTIL ALL FIELD WIRING HAS BEEN TESTED.
 - C.) DO NOT INSTALL FIRE ALARM CONTROL PANEL OR ANY ADDRESSABLE DEVICES IN UNHEATED SPACE.
- D.) DO NOT INSTALL ANY AC CURRENT CARRYING CONDUCTORS CLOSE TO OR IN THE SAME RACEWAY WITH FIRE ALARM SYSTEM CONDUCTORS.
- E.) SOLID LINES REPRESENT CONNECTIONS MADE BY THE SYSTEM INSTALLER.
- F.) ALL RELAYS ARE SHOWN IN NORMAL SUPERVISORY CONDITION. ALL RELAYS ARE FORM "C" TYPE.

INSTALLATION NOTES

- A.) SMOKE DETECTORS SHALL NOT BE MOUNTED ANY CLOSER THAN 3' FROM ANY AIR DUCT OPENINGS.
- B.) ELEVATOR LOBBY SMOKES SHALL BE MOUNTED WITHIN 10' OF THE ELEVATOR DOOR.
- C.) MANUAL PULL STATIONS SHALL BE MOUNTED PE ADA REQUIREMENTS: 48" AFF OR 42" AFF TO COMPLY WITH SIDE/FRONT REACH REQUIREMENTS.
- D.) WALL MOUNTED HORN STROBES AND STROBES SHALL BE MOUNTED 6" FROM CEILING, OR 96" TO 80" AFF TO THE CENTER OF THE STROBE.
- E.) HORN STROBES AND STROBES SHALL BE MOUNTED 15" FROM THE CORNER OF THE WALL. IF THIS IS NOT POSSIBLE, DEVICE SHALL BE CENTERED ON THAT WALL.
- F.) CEILING MOUNTED HALLWAY DEVICES SHALL BE LOCATED IN A SYMMETRICAL MANNER DOWN THE CENTER OF THE HALLWAY WHEN POSSIBLE.