



NOTE:

1. SEE SHEET M-001 FOR LEGEND AND ABBREVIATIONS.

KEYED NOTES:

① REBALANCE SUPPLY FAN TO 5,900 CFM, 3.9 TSP, 1.1 ESP. BALANCER TO DETERMINE IF SHEAVE CHANGE IS REQUIRED TO ACHIEVE AIRFLOW.

DEMOLITION KEY NOTES:

① REMOVE EXISTING DX COIL, ASSOCIATED PIPING, AND CONDENSING UNIT IN ITS ENTIRETY. RECLAIM REFRIGERANT AS REQUIRED.

A1 DEMOLITION ROOF PLAN
1/4"=1'-0"

A7 ROOF PLAN
1/4"=1'-0"

144 Fore Street, P.O. Box 616
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-0700
www.smrinc.com

ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING



MERCY HOSPITAL
EQUIPMENT REPLACEMENT
PORTLAND, ME
ISSUED FOR CONSTRUCTION
9-12-12

REV	DESCRIPTION	DATE
0	ISSUED FOR CONSTRUCTION	9-12-12

GRAPHIC SCALE:
0 1'

SCALE: AS NOTED
PROJECT MANAGER: KD
JC/DRAWN BY: MBD
A/E OF RECORD: TAC
CAD FILE: M-101-12076.DWG
PROJECT NO: 12076
DATE: -

SHEET TITLE:
HVAC
ROOF PLANS

SHEET No.
M-101
© COPYRIGHT 2008 SMRT INC.