

Pinnacle Series

CLAD DOUBLE HUNG

SPECIFICATIONS

PART 2 – PRODUCTS

2.01 MANUFACTURER

- A. Pinnacle Series Aluminum Clad Wood double hung window units [including fixed units] as manufactured by Windsor Windows & Doors.

2.02 MATERIALS

- A. Frame: Shall be select softwoods treated with water repellent preservative in accordance with NWWDA I.S.-4-81, assembled with hardware installed. Exposed exterior portion shall be extruded aluminum cladding sealed at the corners with closed cell foam gaskets. Jamb thickness shall be 11/16". Jamb width shall be 4-9/16". Jamb extenders are available to match other finished wall thicknesses. Aluminum sill is thermally broken and end sealed. Vinyl hinged nailing fin and drip cap are utilized for installation. Rigid aluminum nail fin and color matched drip cap option is available. Natural Alder and Fir interior options are available. DP Upgrade units receive a 1/2" taller inside sill stop.
- B. Sash: Wood interior shall be select pine treated with water repellent preservative. Corners shall be coped and stapled. Exterior surfaces shall consist of aluminum extrusion with lapped corners held together by color-matched injected-molded corner keys. Foam tape is applied to the back side of glass stop. Natural Alder and Fir interior option is available. DP upgrade units shall have no finger pulls. No finger pull option is available for standard units.
- C. Finish: All aluminum exterior surfaces shall be covered with factory applied, baked on acrylic finish in bronze, white, tan, ivory, hunter green, cinnamon, and black. Custom, Feature, and Anodized colors are also available.
- D. Glazing: Shall be 3/4" double pane LoE 366 insulating glass as standard, glazed with double-faced tape plus a full perimeter bead of silicone, and interior wood stops. A wide array of other glass options is offered including clear, tinted, tempered, and obscure. Cardinal's Preserve™ option is available on all LoE 366, glass. It is a removable, factory-applied protective film adhered to both interior and exterior surfaces of the glass.
- E. Weatherstripping: Shall be closed-cell foam encased in TPE skin installed at the head, checkrail, and sill. Flex-hinge jambliner provides a tight seal at the stiles.
- F. Hardware: Extruded vinyl jambliners shall have dual hinged leaf compression legs: beige color standard. White jambliner option available. Spring-loaded die-cast tilt latches allow both sash to be tilted in with ease. Balance system consists of a block and tackle with a locking shoe that allows for easy cleaning or removal; where required by sash weight, a double spring balance will be substituted. Flange mounted cam action locks have contemporary curved handle and concealed fasteners. One lock is used on unit widths 24" and below. Two locks are used on unit widths of 28" on up. Locks, keepers, and tilt latches all have a baked on champagne enamel finish. White, black, bronze, brass, oil-rubbed bronze, and satin nickel hardware options available.
- G. Screens: Shall be a fiberglass BetterVue™ screen set in painted aluminum frame. UltraVue™ Screen option is available. Screens are full height of opening. Screens available in white, bronze, tan, ivory, hunter green, cinnamon, or black. The screen is intended to allow air and light in and keep insects out. The screen is not intended to stop children, adults or animals from falling out an open window.
- H. Grilles: (Extra when specified) Colonial grilles shall be select pine with moulded edges. Stick grilles are fastened to sash with press pins, while perimeter grilles use a hidden clip system. Stick grilles and perimeter grilles are available in 7/8" or 1-1/4" widths. White, cinnamon, bronze, tan, ivory, hunter green, or black; aluminum inner grilles (in air space) are also available in 13/16" flat, 3/4" profiled, or 1" profiled. Two-toned inner grilles (3/4" profiled only) are available with a white interior, and a bronze, green, tan, ivory, or black exterior. Windsorlite (WDL) simulates true divided lite, but is created by adhesively fixing the wood interior and aluminum exterior to the surfaces of the insulated glass; when ordered interior primed, the interior WDL bars will be cellular PVC. WDL is available in 7/8" and 1-1/4" standard, 5/8" putty, and 7/8" putty with standard interior. All are available with or without inner bar between the glass. Exterior bars are available in bronze, white, tan, ivory, hunter green, cinnamon, or black.