NORRIS INC

PO Box 2551
2257 West Broadway
South Portland, ME 04106

1.800.370.3473
fax 207.879.0540

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 09/02/13

6/3/13

Scope of Work: 100 State St. Fire Alarm Replacement

The customer was experiencing problems with the existing fire alarm control panel—Notifier 5000. This is a conventional style panel that has been discontinued for some time. Customer has decided to replace the fire alarm panel with a new addressable panel and upgrade all initiating devices to addressable type. We are only proposing to replace the existing conventional devices in their current locations. All existing horn strobes and strobes will remain in place.

The main fire alarm panel will be located in the electrical room on the ground floor, and there will be a remote annunciator panel located at the main entrance. There is an existing knox box at the main entrance. There is an existing master box on site which will be replaced with a new AES radio master box. A new fire alarm documents cabinet will be installed next to the main fire alarm panel.

The building is fully sprinkled.

Norris Inc. will install the equipment, program and test per City of Portland requirements.