


QUOTE NBR	CUST NBR	CUSTOMER PO	ENTERED	DATE ORDERED	ORDER TYPE
4443446	1011711		8/6/2018	Quote Not Ordered	Cash
ORDERED BY	STATUS	SHIP VIA	DELIVERY AREA		
AUGI	None	Whse Pickup	SALEM WAREHOUSE		
CLERK		JOB NAME	COUPON		
kg - Karen Greenwood		HANSON			

LINE #	DESCRIPTION	QTY	UNIT PRICE	EXTENDED
11000-1	Vinyl Casement , Unit Size 29.5 x 50.5, RO 30 x 51 Unit 1: U-Factor = 0.25, SHGC = 0.24, VT = 0.43, HII-M-38-02061-00001, Size Options = Custom Size, Replacement, Hinge Left Frame Width (Inches) = 29.5, Frame Height (Inches) = 50.5 Double Glazed, Double Low-E RS, Argon Filled Base Color = White, None Egress Hardware, Operator Arm = Double Fiberglass Mesh Head Expander Overall Frame Width (Inches) = 29.5, Overall Frame Height (Inches) = 50.5, Overall Rough Opening Width (Inches) = 30, Overall Rough Opening Height (Inches) = 51 Clear Opening Width = 22.25, Clear Opening Height = 44.75, Clear Opening Square Footage = 6.91 E.Star Zone:North=Yes, E.Star Zone:North-Central=Yes, E.Star Zone:South=Yes, E.Star Zone:South-Central=Yes	1	\$378.90	\$378.90




Room Location: None Assigned

Pricing Details

Egress Hardware Add-On	\$8.00
Low-E Add-On	\$18.50
Argon Add-On	\$4.00
Vinyl Casement Base Charge	\$331.90
Low-E RS Add-On	\$16.50

LINE #	DESCRIPTION	QTY	UNIT PRICE	EXTENDED
12000-1	Vinyl PW , Unit Size 58.5 x 45.5, RO 58.75 x 46 Unit 1: U-Factor = 0.26, SHGC = 0.32, VT = 0.58, HII-M-10-00936-00001, Size Options = Custom Size, Replacement Frame Width (Inches) = 58.5, Frame Height (Inches) = 45.5 Double Glazed, Low E, Argon Filled, DSB Base Color = White, None Head Expander Overall Frame Width (Inches) = 58.5, Overall Frame Height (Inches) = 45.5, Overall Rough Opening Width (Inches) = 58.75, Overall Rough Opening Height (Inches) = 46 E.Star Zone:North=Yes, E.Star Zone:North-Central=Yes	1	\$317.50	\$317.50



Room Location: None Assigned

Pricing Details

Oversize Add On	\$12.00
Low-E Add-On	\$37.75
Argon Add-On	\$5.00
DSB Glass Add-On	\$15.50
Vinyl Picture Window Base Charge	\$247.25



Reviewed for Code Compliance
 Permitting and Inspections Department
 Approved with Conditions

10/23/2018

QUOTE NBR	CUST NBR	CUSTOMER PO	ENTERED	DATE ORDERED	ORDER TYPE
4443446	1011711		8/6/2018	Quote Not Ordered	Cash
ORDERED BY	STATUS	SHIP VIA	DELIVERY AREA		
AUGI	None	Whse Pickup	SALEM WAREHOUSE		
CLERK	JOB NAME		COUPON		
kg - Karen Greenwood	HANSON				
LINE #	DESCRIPTION	QTY	UNIT PRICE	EXTENDED	

13000-1	Steel 90 Minute Fire Doors , Unit Size 31.625 x 82, RO 32.375 x 82.5 SE210 Call Width = 26, Call Height = 68, Frame Width (Inches) = 31.625, Frame Height (Inches) = 82 Overall Frame Width (Inches) = 31.625, Overall Frame Height (Inches) = 82 Hinge Direction (As Viewed From the Outside) = Hinge Right, In-Swing Steel, 4 1/2 " - 5 1/2", Standard Bore Lockset Only, Plymouth, F10 - Passage Set, Standard Bright Brass, No Keying Required, Self-Closing Bommer Hinges Fire Rating = 90 Minute Rating	1	\$464.00	\$464.00	
---------	--	---	----------	----------	--



Room Location: None Assigned

Pricing Details

Therma-Tru Lockset Charge	\$15.00
TT Hinge Charge	\$39.00
Therma-Tru Slab Charge	\$200.00
Fire Door Label Charge	\$10.00
Wrapping Therma-Tru Frame	\$200.00

****Note: Delivery charges may apply and are not included on this quote.**

This quotation is based on our interpretation of the information provided. All quantities, sizes, extensions, grand totals, and specifications should be verified by the contractor prior to his/her bidding or ordering of materials. Harvey Industries, Inc., is responsible only for the items as quoted above. Any changes or addendums will be subject to a requote. We propose to supply the materials as described above, subject to the terms and conditions as required by our credit department. The prices are guaranteed for 30 days from the date of quotation unless otherwise noted. Delivery charges may apply and are not reflected on this quote. We appreciate the opportunity to quote this job. If you have any questions, please call your local warehouse.

SUBTOTAL:	\$1,539.30
TAX:	\$0.00
ORDER TOTAL:	\$1,539.30

CUSTOMER SIGNATURE _____ DATE _____



Reviewed for Code Compliance
Permitting and Inspections Department
Approved with Conditions

10/23/2018

Property

86 Winter St. Portland ME, 04102

Owner – Carl Hanson

10 Romasco Lane Portland ME 04102

(207)-272-2518

Contractor – Augi Traynor

50 Lane Rd. Raymond, NH 03077

(603)-300-6386 augi.traynor@gmail.com

This is a four unit residential housing.

One window must be replaced to meet egress requirements. See 1

Laundry room door must be replaced with a fire rated door. See 2

1: Third story bedroom:

Replace a replacement style double hung with replacement style casement window.

White Harvey replacement casement window with egress hinge.

11000-1 Vinyl Casement , Unit Size 29.5 x 50.5, RO 30 x 51 Unit 1:

U-Factor = 0.25, SHGC = 0.24, VT = 0.43, HII-M-38-02061-00001,

Double Glazed, Double Low-E RS, Argon Filled

Overall Frame Width (Inches) = 29.5, Overall Frame Height (Inches) = 50.5,

Overall Rough Opening Width (Inches) = 30, Overall Rough Opening Height (Inches) = 51

Clear Opening Width = 22.25, Clear Opening Height = 44.75, Clear Opening Square Footage = 6.91

E.Star Zone:North=Yes, E.Star Zone:North-Central=Yes, E.Star Zone:South=Yes, E.Star Zone:South-Central=Yes



2: Common laundry room:

Replace wooden interior door with steel door.

90 Minute fire rated steel door, steel frame.

Self-closing bommer hinges and passive handle set.



Reviewed for Code Compliance
Permitting and Inspections Department
Approved with Conditions

10/23/2018