Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 03/12/15

NOTES:

1.) CABINETRY AND COUNTERS BY OWNER

2.) G.C TO PROVIDE FINISHED ELECTRICAL SYSTEM PER CODE AND COORDIANTE WITH OWNERS EQUIPMENT

3.) G.C. TO PROVIDE ROUGH PLUMBING TO LOCATIONS OF SINK, DISHWASHER, ESPRESSO MACHINE

4.) G.C. TO PROVIDE FINISHED BATHROOM SIMILAR TO ORIGINAL PLAN (BUT IN NEW LOCATION)

5.) G.C. TO PROVIDE HUNG 5/8" GWB CEILING WITH PAINTED FINISH, PROVIDE ACCESS PANELS AS REQUIRED

6.) PROVIDE DIMMERS AND DIMMABLE FIXTURES FOR ALL LIGHTING

REFLECTED CEILING PLAN

SCALE 1/4" = 1'-0"

COFFEE SHOP PLAN

SCALE 1/2" = 1'-0"

EQUIPMENT SCHEDULE

TYPE	MANUFACTURER	MODEL	ELECTRICAL INFO
ESPRESSO MACHINE	BLACK EAGLE	2 HEAD UNIT	208-240V, 7100 WATTS, 32 AMP DRAW, NEMA 6-50
UNDERCOUNTER REFRIGERATOR	TRUE	TUC-48	1/5 HP, 115V/60/1, 5.0 AMPS, NEMA 5-15P
DISHWASHER	CMA	UC65e	208-240v/60/1-PH, STANDARD
ICE MACHINE	MANITOWOC	UR 140A	G.C. TO CONFIRM
WATER TOWER	MARCO		2.8kW-230V-50Hz
GRINDER	MYTHOS		110 volts, 800 watts, amp draw 8, nema 5-15 RECEPTACLE
3 BAY SINK	KROWNE	#18-33	
GRINDER	MAHLKONIG	GSS1	110-115 V, 60 HZ SINGLE PHASE

© 2014 RYAN SENATORE
ARCHITECTURE

WEST END PLACE

44 PINE STREET
PORTLAND, MAINE

RSA
RYAN SENATORE
ARCHITECTURE
67 GRAY ROAD
GORHAM, MAINE 04038
207-650-6414
senatorearchitecture.com

CONSULTANTS:

REVISIONS:

REVISION #1 - 02/27/15

DATE: NOVEMBER 12, 2014

PROJECT No.

DRAWN BY: RJS

CHECKED BY: RJS

SCALE: AS NOTED

SHEET TITLE:

ASK
13