

Rufus Deering Co
383 Commercial Street
Portland, ME 04101
Phone: (207) 772-6505

QUOTE BY: scook

QUOTE #: J11500230

SOLD TO: MARK LENARD


SHIP TO:

PROJECT NAME: WINTER STREET

LINE NO.	LOCATION SIZE INFO	BOOK CODE DESCRIPTION	UNIT PRICE	QTY	EXTENDED PRICE
----------	-----------------------	--------------------------	---------------	-----	-------------------

Line-3

Pocket Opening: 34 1/8 X 61 1/4



Viewed from Exterior. Scale: 1/4" = 1'

Frame Size : 33 5/8 X 61
 Tradition Plus Wood Double Hung, Auralast Pine, Pocket Unit,
 Pocket Opening = 34 1/8 X 61 1/4
 Primed Exterior,
 Primed Interior,
 White Jambliner,
 White Hardware,
 BetterVue Mesh Brilliant White Screen, Half Screen,
 US National-WDMA/ASTM, PG 35,
 Insulated Low-E Annealed Glass, Argon Filled, ←
 5/8" Putty SDL w/Perm Wood Primed Wood SDL, Silver Shadow Bar,
 Colonial All Lite(s) 3 Wide 2 High Top 2 High Btm,
 3 1/4" Pocket
 U-Factor: 0.30, SHGC: 0.24, VLT: 0.45, CPD: JEL-N-843-00548-00001
 PEV 2014.2.1.1061/POV 6.066 (06/10/14) CW

*2 SIDES
AND DEAR
AWARD BITTERS
SUBSET SPAR*


\$639.20

1

\$639.20

Line-2

Pocket Opening: 34 1/8 X 61 1/4



Viewed from Exterior. Scale: 1/4" = 1'

Frame Size : 33 5/8 X 61
 Tradition Plus Wood Double Hung, Auralast Pine, Pocket Unit,
 Pocket Opening = 34 1/8 X 61 1/4
 Primed Exterior,
 Primed Interior,
 White Jambliner,
 White Hardware,
 BetterVue Mesh Brilliant White Screen, Half Screen,
 US National-WDMA/ASTM, PG 35,
 Insulated Clear Annealed Glass, ←
 5/8" Putty SDL w/Perm Wood Primed Wood SDL, Silver Shadow Bar,
 Colonial All Lite(s) 3 Wide 2 High Top 2 High Btm,
 3 1/4" Pocket
 U-Factor: 0.46, SHGC: 0.51, VLT: 0.53, CPD: JEL-N-843-00542-00001
 PEV 2014.2.1.1061/POV 6.066 (06/10/14) CW

*FRONT
UNITS*

\$624.51

1

\$624.51