

REVISED
PROPOSAL
SUBMITTED
(4/10)

46 Avon Street

Deck and stair project construction notes:

1. All framing and supports to be PT wood.
2. Decking to be pressure treated 5/4 wood
3. Deck and stair rails, posts and balusters to be white composite/vinyl or equivalent. Rail height will be to code (expected at 38"). Composite balusters will be square approximately 1.5" and spaced at 3.5" apart. Guard rail posts and handrail posts will be covered in white composite material and capped. (structural measurement will be 3.5"X3.5", finished size will be approximately 4" X 4") See attached copy from CertainTeed catalog.
4. Stairs will have PT treads and solid white painted risers. Approximate stair rise will be 7.75" and run will be 10.5"
5. Entry door will be Thermatru (or equivalent) 3-0/6-8 colonial style fiberglass door with 9 light or 15 light glass)