Reviewed for Code Compliance
Inspections Division
Date: 10/23/17

KEY
SEE LIGHTING SCHEDULE FOR MORE INFORMATION

- RECESSED CEILING FIXTURE
- SURFACE MOUNT CEILING FIXTURE
- PENDANT FIXTURE
- WALL SCONCE
- POST LIGHT
- CABLE TRACK LIGHTING
- LED TUBE LIGHT
- 12V LINEAR LED W/ REMOTE TRANSFORMER, 2700K
- RECESSED CEILING FIXTURE W/ GIMBAL
- EXTERIOR FLOOD LIGHT
- -EX DENOTES EXISTING FIXTURE
- EXTERIOR RECESSED FLOOR FIXTURE
- RECESSED CEILING FIXTURE (EXTERIOR)
- PLUG MOLD
- WALL SWITCH
- DIMMER SWITCH
- 3-WAY WALL SWITCH
- 4-WAY WALL SWITCH
- FAN SWITCH
- JAMB SWITCH
- DUPLEX RECEPTACLE
- SWITCHED RECEPTACLE
- 220 VOLT RECEPTACLE
- GFI RECEPTACLE
- DATA AND/OR TV
- FL FAN/LIGHT COMBO FIXTURE
- THERMOSTAT
- RECESSED CEILING SPEAKER
- DUPLEX FLOOR RECEPTACLE
- CO/SMOKE DETECTOR
- SCHEDULE TAG

NOTES:

ELECTRICAL CONTRACTOR TO SCHEDULE ON-SITE REVIEW OF PROJECT PRIOR TO ROUGH-IN.

CENTER SWITCHES AT 42" AFF UNLESS OTHERWISE NOTED.

CENTER OUTLETS AT 16" AFF UNLESS OTHERWISE NOTED.

OUTLETS TO BE LOCATED PER PLANS, ADD OUTLETS AS REQ'D BY CODE.

SMOKE DETECTORS/CO TO CODE.

NO MORE THAN 4 SWITCHES GANGED IN ONE BOX. IF MORE THAN 4 SWITCHES ARE REQUIRED, STACK 2 BOXES ABOVE ONE ANOTHER WITH EQUAL NUMBER OF SWITCHES IN EACH BOX. USE DUMMY SWITCH IF NECESSARY.

BATH FAN/LIGHTS TO BE PANASONIC UNITS, FANS TO BE ON TIMER SWITCHES.

SECOND FLOOR HEAT: RADIANT MATS AT BATHROOMS

COMMUNICATION: N/A

2 PARTIAL FIRST FLOOR ELEC. PLAN
1/4" = 1'-0"

ELECTRICAL SCHEDULE

Tag	Description	Model	Manuf.	Finish	Lamp	Wattage	Voltage	Mounting	Qty	Remarks
A	Surface Mount	TBD	TBD	TBD				Ceiling	5	
B	Wall Sconce	TBD	TBD	TBD				Wall	2	(Allow $200/per fixture)
C	24" LED Tube Light	TBD	TBD	TBD				Ceiling/wall	3	
D	Surface Mount	TBD	TBD	TBD				Ceiling	3	
E	Exhaust Fan/Light	WhisperGreen Select FV- 11 VQCL6	Panasonic					Recessed Ceiling	3	110 CFM, 0.7 sone ceiling fan with motion and humidity sensors and CFL light. Use Panasonic FV-WCD02 Whisper Control 4 Function Light Switch
F	Recessed light (wet location)	RZR-600-12W-3K-SC	NDR Electric	Satin Chrome		12W	120	Recessed Ceiling	1	3000k, 950 Lumens
G	Surface Mount	TBD	TBD	TBD				Wall	2	(Allow $200/per fixture)

1 ELECTRICAL PLAN
1/4" = 1'-0"

0 2' 4' 8' 16'

© COPYRIGHT 2017 MICHAEL MAINES RESIDENTIAL DESIGN, LLC

MICHAEL MAINES RESIDENTIAL DESIGN
336 N PALERMO RD
PALERMO, ME 04354
207-318-6224
mike@michaelmaines.com

RENOVATIONS TO THE
RECORD / CORBIN APARTMENT
29 DEERING STREET #2 - PORTLAND, MAINE 04101

ISSUED FOR PERMITTING & CONSTRUCTION

DATE	June 14, 2017
REV	
REV	

SHEET E101