

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

BURNHAM PROPERTIES LLC

Located at

17 DEERING ST

PERMIT ID: 2016-01544

ISSUE DATE: 08/11/2016

CBL: 046 B019001

has permission to **Fire Alarm install**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 HOUR NOTICE IS REQUIRED.	A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.
---	--

/s/ Michael White

/s/ Tammy Munson

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Building Inspections

Fire Department

19 dwelling units

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

**Check the Status or Schedule an Inspection On-Line at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the City of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that are attached to this permit! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases 6 months.**
- **If the inspection requirements are not followed as stated below, additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**

REQUIRED INSPECTIONS:

Fire Inspection

Final Inspection

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2016-01544	Date Applied For: 06/09/2016	CBL: 046 B019001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Multi family	Proposed Project Description: Fire Alarm install			
Dept: Historic Status: Approved w/Conditions Reviewer: Robert Wiener Approval Date: 08/08/2016				
Note:				Ok to Issue: <input checked="" type="checkbox"/>
Conditions:				
1) No exterior alterations are approved with this permit, including but not limited to wiring, conduit, horns, strobes, etc. If any exterior work is anticipated it must be reviewed and approved in advance.				
<hr/>				
Dept: Zoning Status: Approved Reviewer: Christina Stacey Approval Date: 07/28/2016				
Note:				Ok to Issue: <input checked="" type="checkbox"/>
Conditions:				
<hr/>				
Dept: Fire Status: Approved w/Conditions Reviewer: Michael White Approval Date: 07/29/2016				
Note:				Ok to Issue: <input checked="" type="checkbox"/>
Conditions:				
1) A 4100 series Knox Box is required.				
2) All fire alarm records required by NFPA 72 should be stored in an approved cabinet located at the FACP labeled "FIRE ALARM RECORDS".				
3) Supervising Station monitoring for addressable fire alarm systems shall be by point.				
4) Automatic fire detection devices shall be installed as follows:				
(1) Smoke detectors shall be installed in all common areas and work spaces outside the living unit, such as exit stairs, egress corridors, lobbies, storage rooms, equipment rooms, and other tenantless spaces in environments suitable for proper smoke detector operation.				
(2) Heat detectors shall be located within each room of the living unit (exception: bathrooms not exceeding 55 ft ² and closets not exceeding 24 ft ² and no more than 3 ft. deep).				
5) Manual Pull Stations are required per NFPA 101:30.3.4.2.1 at all exit doorways and within 200 feet of travel.				
6) The fire alarm system shall have a new fire alarm inspection sticker.				
7) The installation shall comply with the following:				
City of Portland Chapter 10, Fire Prevention and Protection;				
NFPA 1, Fire Code (2009 edition), as amended by City Code;				
NFPA 101, Life Safety Code (2009 edition), as amended by City Code;				
City of Portland Fire Department Rules and Regulations;				
NFPA 72, National Fire Alarm and Signaling Code (2010 edition), as amended by Fire Department Rules and Regulations; and				
NFPA 70, National Electrical Code (2011 edition) as amended by the State of Maine				
8) Fire protection systems shall be maintained. If system is to be off line over 4 hours a fire watch shall be in place. Dispatch notification required 874-8576.				
9) All smoke alarms shall be photoelectric.				
10) Visible signals are required per NFPA 101:9.6.3.5 in accordance with NFPA 72:18.5.4.4. Audible and visible notification signals are not required in exit stair enclosures by NFPA 101:9.6.3.5.5 and NFPA 101:9.6.3.6.4.				
11) NFPA 1 Fire Code Per 1.14.4 Review and approval by the AHJ shall not relieve the applicant of the responsibility of compliance with this Code.				