

**CITY OF PORTLAND
PORTLAND FIRE DEPARTMENT**

380 Congress Street
Portland, Maine 04101

Inspection Violations

Owner/Manager Thomas Reed House Llc		Inspector David Petruccelli	Inspection Date 6/11/2015
Location 0030 DEERING ST	CBL 046 C001001	Status Failed	Inspection Type Fire Prevention-FP Routine Inspe

Code	Int/Ext	Floor	Unit No.	Area	Compliance Date
------	---------	-------	----------	------	-----------------

1) 69.20

Violation: PORTLAND FIRE DEPARTMENT CHAPTER 10 SECTION 12 KNOX BOX REQUIRED; KNOX BOXES ARE REQUIRED FOR ALL BUILDINGS WITH FIRE ALARM OR SUPPRESSION SYSTEMS.

Notes:

2) 69.25

Violation: PORTLAND FIRE DEPARTMENT CHAPTER 10 4.6.1, 4.6.2 UNIT/SUITE NUMBERS NOT MARKED; 4.6.1 RESIDENTIAL UNITS SHALL BE DESIGNATED USING NUMERALS.

4.6.2 THE FIRST NUMERAL OF EACH RESIDENTIAL UNIT SHALL BE THE FLOOR DESIGNATION.

Notes:

3) 73.05

Violation: NFPA 101- 7.2.1.15.8 FIRE DOOR ASSEMBLY REQ REPAIR; DOOR OPENINGS NOT IN PROPER OPERATING CONDITION SHALL BE REPAIRED OR REPLACED WITHOUT DELAY.

Notes:

4) 73.10

Violation: NFPA 101-7.2.4.3.1 FIRE BARRIER REQUIRES MAINTENANCE; Fire barriers separating buildings or areas between which there are horizontal exits shall have a minimum 2-hour fire resistance rating, unless otherwise provided in 7.2.4.4.1, and shall provide a separation that is continuous to the finished grounded level.

Notes:

5) 73.15

Violation: NFPA 31.3.1.1.1 VERTICAL OPENINGS NOT FIRE RATED; VERTICAL OPENINGS SHALL BE ENCLOSED OR PROTECTED IN ACCORDANCE WITH SECTION 8.6.

Notes:

6) 73.30

Violation: NFPA 101-31.3.4.1.1 FIRE ALARM SYSTEM REQUIRED; Apartment buildings four or more stories in height or with more than 11 dwelling units, other than those meeting the requirements of 31.3.4.1.2, shall be provided with a fire alarm system in accordance with Section 9.6, except as modified by 31.3.4.2 through 31.3.4.6.

Notes:

7) 80.46

Violation: NFPA 101- 7.2.1.8.1 FIRE DOORS MUST BE SELF- OR AUTO-CLOSING; A door leaf normally required to be kept closed shall not be secured in the open position at any time and shall be self-closing or automatic-closing in accordance with 7.2.1.8.2, unless otherwise permitted by 7.2.1.8.3.

Notes:

CITY OF PORTLAND
PORTLAND FIRE DEPARTMENT

380 Congress Street
Portland, Maine 04101

Inspection Violations

Owner/Manager Thomas Reed House Llc		Inspector David Petruccelli	Inspection Date 6/11/2015
Location 0030 DEERING ST	CBL 046 C001001	Status Failed	Inspection Type Fire Prevention-FP Routine Inspe

8) 80.80

Violation: NFPA 101- 7.5.1.1.1 SECOND EXIT REQUIRED; Where exits are not immediately accessible from an open floor area, continuous passageways, aisles, or corridors leading directly to every exit shall be maintained and shall be arranged to provide access for each occupant to no less than two exits by separate ways of travel, unless otherwise provided in 7.5.1.1.3 and 7.5.1.1.4.

Notes:

9) 80.82

Violation: NFPA 101- 7.2.2.5.1.1 EXIT STAIRS NOT SEPARATED.; ALL INSIDE STAIRS SERVING AS AN EXIT OR EXIT COMPONENT SHALL BE ENCLOSED IN ACCORDANCE WITH 7.1.3.2.

Notes:

10) 91.10

Violation: NFPA 70- ARTICLE 110 B CERTIFY ELECTRICAL SYSTEM; LISTED OR LABELED EQUIPMENT SHALL BE INSTALLED AND USED IN ACCORDANCE WITH ANY INSTRUCTIONS INCLUDED IN THE LISTING OR LABELING.

Notes:

11) 3.011

Violation: NFPA 101- 31.3.2.1.1 BOILER PROTECTION REQUIRED; THE AREAS DESCRIBED IN TABLE 31.3.2.1.1 SHALL BE PROTECTED AS INDICATED:
BOILER AND FUEL-FIRED HEATER ROOMS SERVING MORE THAN A SINGLE DWELLING UNIT (MINIMUM SEPARATION/PROTECTION IS 1 HOUR OR SPRINKLERS)

Notes:

Comments: Check on status of property sale and plan to correct outstanding violations, for 30 & 32 Deering. Bill Simpson seller