## **HVAC BID-PROPOSAL**

This form complies with professional standards in effect January 1-December 31, 2015



# DAVE'S APPLIANCE, INC.

"Quality Service ... Always" 59 Central Street Winthrop, ME 04364

DATE: July 8,, 2016 PROPOSAL NO: 0708167E

PHONE (800) 298-8858 LOCAL (207) 377-8858

and **BUYER/ OWNER** 

Bill Doukas			
PROJECT ADDRESS	CITY	STATE/ZIP	PHONE
195 State Street	Portland	ME 04101	318.9234
ALTERNATE ADDRESS (IF ANY)	CITY	STATE/ZIP	PHONE

HVAC Project To Be	gin: Upon Approval	Contract Completion Date: 2 Business Days				
Date Of Plans:	Architect:	Engineer:				
Work performed at	195 State Street Portland, Maine					
(Street Address And Legal Description of Known)						

We hereby propose to furnish the following HVAC work:

### **OPTION 1: SINGLE UNIT-1ST LEVEL**

Install one 15K BTU wall mount evaporator, Fujitsu Model ASU15RLS3 in the living room. Line set to exit out and run across top of window, over and down to connect to matching outdoor condenser unit, Fujitsu Model AOU15RLS3H mounted to a wall bracket secured to the wall.

Price: \$3569

#### **OPTION 2: MULTI UNIT- 1 UP/1 DOWN**

Install one 12K BTU wall mount evaporator, Fujitsu Model ASU12RLS3 in the living room. Line set to exit out and run across top of window, over and down.

Install one 12K Floor mount evaporator, Fujitsu Model AGU12RLF in the master bedroom. Line set to run into knee wall, across, out through soffit and down. Both interior units to connect to a common outdoor condenser unit, Fujitsu Model AOU24RLXFZH mounted to a wall bracket secured to the wall.

Price: \$6579

#### **NOTES:**

- ► All refrigerant lines will be pressurized and leak checked, purged and vacuumed
- ▶ Dave's Appliance, Inc. is a Fujitsu factory trained Elite Contractor. Warranty is increased from 5 year parts, 7 year compressor to 12 years parts, 12 years compressor.
- ▶ Pricing includes 1 year labor warranty to compliment manufacturers 12 year parts, 12 year compressor warranty
- ► Extended labor warranty of 5 or 10 years available at additional cost
- ▶ Labor quote is estimated. Actual time will be billed upon completion and will not exceed estimate
- ▶ Outdoor power disconnect installation is not included in this quote.
- ▶ Disconnect to be installed by a licensed Master Electrician. Disconnect to be located within 4 feet of outdoor unit.
- ► Single type outdoor units require a 220V 20A Circuit
- ► Multi type outdoor units require a 220V 30A circuit

© 2015 ABCAForms. Rev#2011111500001

Available Accessories: INITIAL BOX TO ACCEPT  [ ] Rain cap for outdoor unit: \$169 single condenser, \$209 [ ] ICM517 Surge Protector for outdoor power disconnect: [ ] Wired Remote Controller UTY-RVNUM Backlit and include [ ] WiFi controller with Smart Phone App: \$229 per indoor [ ] 5 year extended labor warranty: \$249 per outdoor unit [ ] 10 year extended labor warranty: \$399 per outdoor unit	\$79 des room temperature: \$299, installed, per indo unit	or unit
PROPOSED PAYMENT: Owner agrees to pay Contractor a total p (1) Down payment of \$50%,  Down payment due with signed proposal to secure scheduling, eq (2) Balance due upon completion of job.		
NOTE: This proposal may be withdrawn by us if not acceptance of the undersigned agrees to pay the amount stated in said proposal and	OF PROPOSAL accomplish the work described in the above proposal,	for which
	X OWNER/BUYER SIGNATURE X OWNER/BUYER SIGNATURE	/15 DATE /15 DATE

2

© 2010 ABCAForms.