CUNNINGHAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Security Systems

Date: 06/27/14

10 Princes Point Road Yarmouth, Maine 04096
Phone: 207-846-3350 Fax: 207-846-6080

Proposal Submitted To:	Tyler Brinkmann	Date:	May 1, 2014
Company Name:	Marathon Removal & Recycling	System Type:	F
Mailing Address:	10 Clifton Road	Telephone:	653-1798
City:	Falmouth	Fax:	.
State:	ME	Email:	tylerbrinkmann@yahoo.com
Zip Code:	04105	Property:	767 Congress Street

We hereby submit specifications and estimates for:

Installation of a monitored fire alarm system to include the following:

One Fire Lite MS9050 addressable fire alarm control panel
One ANN80 annunciator keypad
One City of Portland Knox Box
One City of Portland document box
Eight SD355 smoke detectors
Two H355 heat detectors
Six MMF300 monitoring modules (sprinkler connections & hood suppression system connection)
Twelve P2R horn/strobes
Six SR strobes
Two MHR mini horns
Plans, permits & submittals

Total Installed Cost: $14,211.00
Monitoring and Dispatch To Be Billed Annually: $312.00 (requires two phone lines)

This proposal is subject to review and acceptance by the local authority (ies) having jurisdiction and subsequent issuance of a fire alarm permit as required by city of Portland inspection services and fire prevention offices.

We propose to furnish material and labor in accordance with the above specifications, for the sum of:

Fourteen Thousand Two Hundred Eleven and 00/100	DOLLARS	$14,211.00

Payments to be made as follows:	Upon completion and receipt of invoice.

This proposal may be withdrawn by us if not accepted within 60 days

Acceptance of Agreement:

Signature: Date:

The above prices, specifications and payment terms are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.