Collins Construction & Consulting

6 Canterbury Pines Drive
Gorham, ME 04038
(207) 939-6406

andrew@collinsconsult.net
www.collinsconsult.net

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 07/27/17

Room: Play Area/Room **Height: 8'**

318.78	SF Walls	138.17	SF Ceiling
456.95	SF Walls & Ceiling	138.17	SF Floor
15.35	SY Flooring	39.00	LF Floor Perimeter
44.08	LF Ceil. Perimeter		

Door	**2' 6" X 6' 8"**	**Opens into UTILITY_ROOM**
Door	**2' 7" X 6' 8"**	**Opens into BDRM_2**
Missing Wall	**3' 5 1/4" X 8'**	**Opens into HALLWAY**

CAT	SEL CALC	ACT DESCRIPTION QNTY	REMOVE	REPLACE	TOTAL
12. PNT	P+	Paint the surface area - one coat - 2 colors			
	535	535.00 SF	0.00+	0.73 =	390.55

Room Totals: Play Area/Room **390.55**

Room: closet 1 **Height: 8'**

87.72	SF Walls	9.75	SF Ceiling
97.47	SF Walls & Ceiling	9.75	SF Floor
1.08	SY Flooring	10.30	LF Floor Perimeter
14.30	LF Ceil. Perimeter		

Door	**4' X 6' 8"**	**Opens into BRDM_1**

CAT	SEL CALC	ACT DESCRIPTION QNTY	REMOVE	REPLACE	TOTAL
13. DRY	1/2MR+	1/2" mold resistant - hung, taped, floated ready for paint			
	W	87.72 SF	0.00+	1.81 =	158.77
14. PNT	P+	Paint the surface area - one coat - 2 colors			
	535	535.00 SF	0.00+	0.73 =	390.55