

1 S1.1 FOUNDATION PLAN
1/8" = 1'-0"

0' 2' 10' 20'

NOTES:

1. ALL CONCRETE REINFORCING STEEL PER PLANS AND SECTIONS.
2. STEP IN TOP OF FOUNDATION WALL IS INDICATED THUS: , AND SHOWS LOWER SIDE OF WALL.
3. SEE S1.0 FOR STRUCTURAL GENERAL NOTES
4. FOOTING TO BEAR 4'-6" MIN BELOW GRADE.
5. T.O. FOOTINGS ARE INDICATED THUS: (XX'-XX"),-TYP. UNO.
6. STEP IN TOP OF FOOTING IS INDICATED THUS: , AND SHOWS LOWER FOOTING.
7. VERIFY ALL USGS ELEVATIONS W/ ARCHITECTURAL AND CIVIL PLANS - TYP.
8. FOOTINGS TO BEAR ON CRUSHED STONE OR NATIVE GLACIAL TIL PER GEOTECHNICAL REPORT - TYP.

2 GENERAL SHEET REVISION: ELEVATION CHANGES AND UPDATES

STATE OF MAINE
AARON C JONES
No. 10968
LICENSED
PROFESSIONAL ENGINEER
1/18/2016

Reviewed for Code Compliance
Inspection Division
Portland, Maine
Date: 07/05/17

Prepared
Bramhall Row, LLC

Consultant:
Structural Integrity
Consulting Engineers
79 Fox Street
Portland, ME 04101
P: 207-774-5445
F: 800-793-7303
JOSH@STRUCTURALINTEGRITY.COM
BUILD@STRUCTURALINTEGRITY.COM
S#16-0137

Architect:
ARCHETYPE architects
48 Union Wharf Portland, Maine
(207) 772-6022;ARCHETYPE@ARCHETYPEPA.COM

Project:
BRAMHALL ROW
749 CONGRESS ST
PORTLAND, MAINE

Revisions
12/30/2016: REV-1 - FOUNDATION
1/19/2017: REV-2 - ELEVATIONS

Scale: 1/8" = 1'-0"

Date: 11 NOV. 2016

FOUNDATION PLAN

S1.1