FRAMING PLAN SYMBOLS KEY	
□	WOOD POST
○	STEEL COLUMN
(X)	NUMBER OF WOOD STUDS IN POST BELOW
A	COLUMN ABOVE THIS LEVEL
C	COLUMN CONTINUOUS THROUGH THIS LEVEL
◄	JOIST BEARING
—	CONTINUOUS JOIST WITH INTERMEDIATE BEARING
T	FLUSH FRAMED JOIST BEARING WITH HANGER
	WOOD STUD BEARING WALL BELOW
"X"T	NUMBER OF TRIM STUDS UNDER HEADER
"X"K	NUMBER OF KING STUDS ADJACENT TO HEADER

1 / S1.5 ROOF FRAMING PLAN
1/8" = 1'-0"

0' 2' 10' 20'

NOTES:

1. SEE SHEET S1.0 FOR GENERAL STRUCTURAL NOTES
2. ALL WOOD COLUMNS IN 2x6 WALLS SHALL BE (3) 2x6 AND IN 2x4 WALLS SHALL BE (3) 2x4 UNLESS NOTED OTHERWISE ON PLANS
3. ALL BEAMS ARE FLUSH, UNO
4. ALL HEADERS IN 2x BEARING WALLS ARE (2) 2X8, UNO
5. ALL ROOF TRUSSES TO BE 14" (MID SPAN) MONO-SLOPE P.E. ROOF TRUSSES @ 16" W/ LSL RIM -TYP UNO
6. ROOF SHEATHING TO BE 5/8" T+G, SEE GENERAL NOTES FOR ADDITIONAL INFORMATION -TYP
7. ALL TRUSS TO TRUSS CONNECTIONS BY MANUFACTURER - TYP UNO.
8. TRUSS DESIGNER TO COORIDINATE TRUSS LAYOUT WITH FLOOR OPENING, PLUMBING, AND UTILITY REQUIREMENTS - TYP.

STATE OF MAINE
AARON C JONES
No. 10968
LICENSED
PROFESSIONAL ENGINEER
11/18/2016

Reviewed for Code Compliance
Inspections Division
Portland, Maine
Date: 07/05/17

Prepared
Bramhall Row, LLC

Consultant:
Structural Integrity
Consulting Engineers
775 Cox Street
Portland, ME 04103
P: 207-797-5411
F: 866-796-7683
INFO@STRUCTURALINTEGRITY.COM
BUILDING DESIGN & ENGINEERING SERVICES
S1#16-0137

Architect:
ARCHETYPE
architects
48 Union Wharf Portland, Maine
(207) 772-6022 ARCHETYPE@ARCHETYPEPA.COM

Project:
BRAMHALL ROW
749 CONGRESS ST
PORTLAND, MAINE

Revisions

Date: 11 NOV. 2016
Scale: 1/8" = 1'-0"
ROOF FRAMING PLAN

S1.5