UNIT DOOR SCHEDULE												
	SIZE			DOOR				FRAME				
DOOR No.	WIDTH	HEIGHT	THICKNESS	TYPE	MATERIAL	FINISH	THRESH	MATERIAL	TYPE	LABEL	FINISH	REMARKS
U01	3'-0"	7'-0"	2 1/4"	1	WOOD/GLASS	VARNISH						UNIT ENTRY DOOR WITH FULL LITE
U02	3'-0"	7'-0"	1 3/4"	6	METAL	PTD						EXTERIOR SWING DOOR
U03	3'-0"	6'-8"	1 3/4"	3	WOOD	PTD						SWING DOOR
U04	2'-8"	7'-0"	1 3/4"	3	WOOD	PTD						SWING DOOR
U05	3'-0"	7'-0"	1 3/4"	3	WOOD	PTD						SWING DOOR
U06	9'-0"	8'-0"	1 3/4"	4	WOOD/GLASS	PTD						SLIDING EXTERIOR GLASS DOOR
U07	8'-0"	8'-0"	1 3/4"	4	WOOD/GLASS	PTD						SLIDING EXTERIOR GLASS DOOR
U08	2'-6"	7'-0"	1 3/8"	3	WOOD	PTD						POCKET DOOR
U09	2'-8"	7'-0"	1 3/8"	3	WOOD	PTD						POCKET DOOR
U10	5'-0"	7'-0"	2"	3	WOOD	PTD						SLIDING CLOSET DOOR
U11	1'-6"	7'-0"	1 3/8"	3	WOOD	PTD						BIFOLD CLOSET DOOR
U12	2'-6"	7'-0"	1 3/8"	3	WOOD	PTD						BIFOLD CLOSET DOOR

UNIT DOORS

8 LEAF TYPES
1/4" = 1'-0"

6 4TH FLOOR UNIT B DOORS
3/16" = 1'-0"

4 3RD FLOOR UNIT B DOORS
3/16" = 1'-0"

7 TYP. CUSTOM OAK DOOR SECTION
1 1/2" = 1'-0"

5 4TH FLOOR UNIT A DOORS
3/16" = 1'-0"

3 3RD FLOOR UNIT A DOORS
3/16" = 1'-0"

2 2ND FLOOR UNIT DOORS
3/16" = 1'-0"

1 1ST FLOOR UNIT DOORS
3/16" = 1'-0"

NOTES

ALL DOOR LEAFS ARE TO BE SOLID STILES AND RAILS WITH STAIN-GRADE VENEER PANEL, U.N.O.

STEEL AND GLASS DOOR SYSTEMS: SEE FINISH SCHEDULE FOR GLAZING TREATMENT

SEE FINISH SCHEDULE FOR LAMINATE GLAZING NOTES

ALL GUEST ROOM CLOSET LEAFS AND BATHROOM STALL LEAFS TO BE 1 3/8" THICK

ALL CLOSET DOORS ARE TO BE OPERABLE

ALL DOORS ARE TO BE PAINT-GRADE, U.N.O.

ALL DOORS OPENING FROM STAIRS A&B TO LEVELS 2-7 ARE TO BE RESTRICT ACCESS TO GUESS ROOM SPACES VIA CARDSWIPE. PROVIDE FAIL SAFE / PANIC BAR FUNCTION FROM CORRIDOR INTO STAIR WELL, TYPICAL.

LICENSED ARCHITECT DAVID LLOYD NO. 936 STATE OF MAINE
Date: 07/05/17

Prepared For: Bramhall Row, LLC

Consultant:

Architect: ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 ARCHETYPE@ARCHETYPEPA.COM

Project: BRAMHALL ROW
749 CONGRESS ST
PORTLAND, MAINE

Revisions:

Scale: As indicated

Date: 21 NOV 2016

DOOR SCHEDULE

A8.01