


CITY OF PORTLAND
 FIRE PREVENTION BUREAU
 380 Congress Street, Portland, Maine 04101
 fireprevention@portlandmaine.gov
 (207) 874-8400



NOTICE OF VIOLATION AND ORDER TO CORRECT

November 17, 2017

Responsible Party 1: UM 42 LLC 6 PHANTOM FARM RD CAPE ELIZABETH, ME 04107		
Location 42 MELLEEN ST	CBL 047 A027001	Inspection Date 10/24/2017
Inspector Philip McGouldrick, Jr	Inspection Type FP Routine Inspection	Status Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must propose a date of completion to remedy each violation, a final date of completion, and a date of re-inspection.

You must send this form to the Fire Prevention Bureau no later than 12/15/2017.

Your failure to submit a plan of action by the date provided, or to correct any violation within the applicable time frame, may result in legal action against you, the imposition of civil penalties, and the pursuit of other legal remedies.

Violation	Proposed Date of Completion
NFPA 101- 31.3.4.5.1 SMOKE ALARMS REQUIRED; In buildings other than those equipped through out with an existing, complete automatic smoke detection system, smoke alarms shall be installed in accordance with 9.6.2.10, as modified by 31.3.4.5.2, outside every sleeping area in the immediate vicinity of the bedrooms and on all levels of the dwelling unit, including basements. 3rd floor Alpha bedroom (designated as Back Right single by property management)	IMMEDIATELY install temporary alarms where required. Your signature below indicates that temporary alarms have already been installed.
NFPA 1 EXCESSIVE/DISORDERLY STORAGE; Reference NFPA 1 for excessive fuel-load. Additional clearance required around furnace	<u>1</u> / <u>21</u> / <u>18</u>
NFPA 30- TABLE 9.6.2.1 FLAMMABLE/COMBUSTIBLE LIQUIDS STORAGE EXCEED LIMIT; See NFPA 30 Table 9.6.2.1 for special occupancy limits for flammable and combustible liquid storage. Excess paint, thinners and stains in basement storage	IMMEDIATELY remove all excess flammable/combustible material from the interior of the structure. Your signature below indicates that all excess material has been removed, will not be replaced, and will be properly disposed of or stored elsewhere.
NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED; Refer to NFPA 101- Table 8.3.4.2 that states fire door assemblies for vertical shafts (including stairways, exits, and refuse chutes) are rated and required for 1 hour. Fire doors required all floors front and back leading to any means of egress	<u>2</u> / <u>23</u> / <u>18</u>

1
3 weeks to
be safe

Violation	Proposed Date of Completion
FINAL DATE OF COMPLETED VIOLATION(S)	2 / 23 / 18
FIRE PREVENTION BUREAU RE-INSPECTION OF COMPLETED VIOLATION(S)	2 / 26 / 18

The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

VIOLATOR CERTIFICATION

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.

2/2/18

 Date

Will H. H. H.

 Responsible Party

 Date

 Responsible Party

SEEN AND AGREED

2/6/18

 Date

Capt. JPB

 Fire Prevention Bureau