



Street View - North Elevation



East Elevation



West Elevation



Area of work:

- Install (1) new enlarged basement window (casement, for egress requirements).
- New window to match adjacent windows as closely as possible: (4 light square, or alternate is single light). Wood frame, and sash, paint to match exist windows: Jeld-Wen Siteline, r.o: 32 3/4" x 42 3/4" unit. If divide light, then to be SDL (inside and out with spacer bar in insulated glass).
- Patch enlarged opening with brick and paint to match adjacent brick.
- Cut low concrete retaining wall for well (for exit), adjacent driveway flows up into well (brick or asphalt).