






ENERGYSAVER® DIRECT VENT WALL FURNACES

EnergySaver® Direct Vent Wall Furnaces										
										
Model	EX08C (RHFE-202FTA)		EX11C (RHFE-265FTA)		EX17C (RHFE-434FTA)		EX22C (RHFE-559FTA) / EX22CW (RHFE-559FTA-W)		EX38C (RHFE-1005FTA) / EX38CW (RHFE-1005FTA-W)	
Color	Beige		Beige		Beige		Beige / White		Beige / White	
Gas Type	NG	LP	NG	LP	NG	LP	NG	LP	NG	LP
Input Range (BTU) (Low / High)	3,000 / 8,000		5,500 / 11,000	5,700 / 11,000	8,200 / 16,700		8,200 / 21,500	8,200 / 20,700	13,200 / 38,400	13,200 / 36,500
AFUE Rating	82%		81%		81%		81%		81%	
Fan CFM (CMM) Output (Low / High)	48.3 / 78.6 (1.4 / 2.2)		96.4 / 128.5 (2.7 / 3.6)		111.3 / 141.5 (3.2 / 4.0)		111.3 / 162.7 (3.2 / 4.6)		190.7 / 263.0 (5.4 / 7.4)	
Dimensions - w, h, d Inches (mm)	18.3 x 27.4 x 10.1 (465 x 695 x 257)		18.3 x 27.4 x 10.1 (465 x 695 x 257)		29.9 x 22.9 x 10.1 (760 x 582 x 257)		29.9 x 22.9 x 10.1 (760 x 582 x 257)		36.6 x 26.4 x 13 (930 x 670 x 320)	
Shipping Weight (lbs/kg)	46 lbs / 21 kg		46 lbs / 21 kg		57 lbs / 26 kg		57 lbs / 26 kg		88 lbs / 40 kg	
Power Consumption (Electronic ignition)	41 watts		44 watts		46 watts		56 watts		117 watts	
Standby Power Consumption	Less than 1 watt		Less than 1 watt		Less than 1 watt		Less than 1 watt		Less than 1 watt	
Noise Level dB(A)	27 - 36		31 - 38		33 - 38		33 - 42		39 - 46	
Total Extended Vent (ft/m)	Not Allowed		13 / 4		13 / 4		13 / 4		13 / 4	
Total Vertical Vent (ft/m)	Not Allowed		8† / 2.4		10 / 3		10 / 3		10 / 3	
Certifications	CSA, ICC-ES-PMG		CSA, ICC-ES-PMG		CSA, ICC-ES-PMG		CSA, ICC-ES-PMG		CSA, ICC-ES-PMG	
Warranty*	10 years on the heat exchanger, 5 years on parts, 2 years on labor				10 years on the heat exchanger, 5 years on parts, 2 years on labor					
Approved Altitude - Feet (m)	10,200 (3,109 m)		10,200 (3,109 m)		10,200 (3,109 m)		10,200 (3,109 m)		10,200 (3,109 m)	

† only 5' allowed above 2000' elevation.

*For complete information and details regarding Rinnai's warranty, please visit rinnai.us.